



BENCH MARKS
 B.M. Nail in SWly Corb on Thornton on C/L Mathews Projected 1830 G.W. of C/L Thornton. Elev. 664.85
 B.M. Nail in lead SW Corner Storm Drain Box 34-75 N.Wly of P1 of Curve bet. Thornton & Marlborough. Elev. 663.75

REFERENCES
 Rec. Map 1825 & 1518
 Field Book 592/61, 63 273/280
 Plan No. 1529, 811

- NOTE:**
- 1- City of Riverside will join edge of existing paving to new gutter where possible, or will remove and replace paving where necessary.
 - 2- Trees within R/W which will interfere with proposed construction to be removed by City of Riverside Street Department.
 - 3- Utilities to be relocated by utility companies as required.
 - 4- Any rebuilding of concrete driveway approaches and walkways between curb and property line made necessary by this construction of curb on this project, shall be by and at the expense of the property owner affected.
 - 5- Contractor will remove all obstructions, including driveways, within R/W that will interfere with proposed construction.

REVISIONS			CITY OF RIVERSIDE CALIFORNIA DEPARTMENT OF PUBLIC WORKS	
MARK	DATE	DESCRIPTION	MATHEWS ST. IMPROVEMENT DISTRICT THORNTON ST. TO MARLBOROUGH ST. CURB AND GUTTER	
①	9-13-51	CORRECTED B.M. wdg.		
②	10-9-51	CORRECTED GRADE wdg.		
DESIGNED BY W.J.G.		CHECKED BY N.A.	APPROVED BY	R-105 SHEET 1 OF 1
DRAWN BY D.R.S.		RECOMMENDED BY	 ASSISTANT CITY ENGINEER	
			DATE	May 23, 1951

