



- GENERAL NOTES**
1. It shall be the responsibility of the contractor to clear the right of way in accordance with the provisions of the law as it affects each utility, including irrigation lines and appurtenances and at no cost to the city.
 2. Construction shall be in accordance with City of Riverside, Department of Public Works Specifications No. 401 and Standard Drawings.
 3. Prime coat, seal coat and joint binder are required.
 4. Grading will require a permit under Ordinance No. 3893 for a cut or fill exceeding 100 cubic yards or a fill over 100' in depth.
 5. Trim edge of existing pavement where new paving joins existing paving to a plane straight edge. Construct match-up paving as shown and overlay. Engineer's estimate of pavement overlay is 1 ton.

CRAWLEY, HAWKINS & ASSOC. ENGINEERS & SURVEYORS RIVERSIDE, CALIF. - PH-684-3522 APPROVED: <i>George D. Crawley</i> DATE 10/7/68 RCE 3885		CITY OF RIVERSIDE, CALIFORNIA DEPARTMENT OF PUBLIC WORKS APPROVED BY: <i>[Signature]</i> DATE 10/13/68 OFFICE ENGINEER DATE DEPARTMENT: 10/13/68 TRAFFIC DIVISION: 10/13/68 ASSISTANT CITY ENGINEER: 10/13/68		STREET PLAN AND PROFILE GRIFFITH STREET LIBERTY STREET INTERSECTION VACATION OF GRIFFITH ST. SOUTHWEST OF LIBERTY ST. PROJECT NO. R-1320 SHEET 1 OF 1 HORIZ. SCALE: 1" = 40' VERT. SCALE: 1" = 4' FILE NO. 440	
JO. 836	FOR: Roy P. Denny, Inc.	FB 57/18	DESIGNED BY: <i>[Signature]</i>	DRAWN BY: <i>[Signature]</i>	CHECKED BY: <i>[Signature]</i>