



SCALE: 1" = 50'
 F.B. 604/52

NOTE:
 CONTRACTOR SHALL REMOVE HEDGES, SHRUBS ETC. WITHIN THE RIGHT OF WAY THAT WILL INTERFERE WITH SIDEWALK CONSTRUCTION.
 TREES ARE 6.5', WATER METERS AND FIRE HYDRANTS ARE 15' FROM CURB FACE UNLESS OTHERWISE INDICATED.
 DRIVEWAYS HAVE A 5' PROPERTY LINE SIDEWALK. GRADE WILL BE SET TO MEET EXISTING DRIVEWAYS AND EXISTING 5' SIDEWALK IN THE FIELD.
 CONTRACTOR SHALL REMOVE THOSE PORTIONS OF THE CONCRETE STRIPS BORDERING DRIVEWAYS WITHIN THE SIDEWALK RIGHT OF WAY.
 CONTRACTOR SHALL PLACE AN EXPANSION JOINT IN THE SIDEWALK AT APPROXIMATELY THE CENTER OF EACH LOT, AND ADJOINING THE CURB RETURNS. WEAKENED PLANE JOINTS WILL BE SPOTTED IN THE FIELD.

| REVISIONS | | | CITY OF RIVERSIDE CALIFORNIA DEPARTMENT OF PUBLIC WORKS | |
|----------------|-------------------------|--------------------------|--|--|
| MARK | DATE | DESCRIPTION | | |
| | | | EILEEN STREET SIDEWALK IMPROVEMENT DISTRICT | |
| DESIGNED BY | CHECKED BY | APPROVED BY | | |
| DRAWN BY | | DIRECTOR OF PUBLIC WORKS | R-151 | |
| RECOMMENDED BY | ASSISTANT CITY ENGINEER | DATE | SHEET 1 OF 1 | |