



**BENCH MARK:**  
60"-22" CSDH BRONZE DISC IN MON.  
VAULT CAPPED AT INTERSECTION OF  
DIANA ST. AND JACKSON ST.

**CONSTRUCTION NOTES:**

1. CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF RIVERSIDE, DEPARTMENT OF PUBLIC WORKS, STANDARD DRAWINGS, AND THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, 1979 EDITION.
2. TRIM EDGE OF EXISTING PAVEMENT WHERE NEW PAVEMENT JOINS TO A SMOOTH, STRAIGHT LINE. CONSTRUCT MATCH-UP PAVING AS SHOWN ON PLAN AND OVERLAY PAVING AS DIRECTED IN THE FIELD TO PRODUCE A SMOOTH SECTION.
3. RIGHTS OF ENTRY HAVE BEEN OBTAINED FOR WORK SHOWN ON PRIVATE PROPERTIES.
4. CONTRACTOR TO GIVE CITY WATER DIVISION FIVE (5) WORKING DAYS WRITTEN NOTICE PRIOR TO START OF CONSTRUCTION AND TO ALLOW CITY TEN (10) WORKING DAYS FOR COMPLETION OF WORK.

- 200 CONSTRUCT CURB AND GUTTER PER STD. DWG. NO. 200, 6" C.F.
- 302 CONSTRUCT DRIVEWAY APPROACH PER STD. DWG. NO. 302
- 1 CONSTRUCT 2 1/2" AL. OVER 4" CRUSHED BASE.
- 2 OVERLAY EXISTING PAVEMENT WITH VARIABLE THICKNESS A.C. TO LIMITS SHOWN ON PLANS.
- 405 CONSTRUCT CATCH BASIN PER STD. DWG. NO. 405.
- 4 GRADE WALKWAY AND DRIVEWAYS TO LIMITS SHOWN ON PLAN.
- 5 REMOVE EXISTING A.C. BERM.
- 6 FENCE TO REMAIN AT EXISTING LOCATION. FENCE POLES TO BE ADJUSTED AS REQUIRED.

CAUTION - PACIFIC TELEPHONE CABLES UNDERGROUND BEFORE EXCAVATING CALL COLLECT

REVISIONS: 1. 1/10/77  
2. 2/10/77  
3. 3/10/77  
4. 4/10/77  
5. 5/10/77  
6. 6/10/77  
7. 7/10/77  
8. 8/10/77  
9. 9/10/77  
10. 10/10/77

CITY OF RIVERSIDE  
PUBLIC WORKS DEPARTMENT

**JACKSON STREET  
WIDENING**  
SOUTHERLY OF A.T. & S.F. R.R., WESTERLY SIDE  
OF JACKSON STREET

R-2126

SHEET 1 OF 1  
DATE: 10/10/77  
SCALE: HORIZ. 1" = 20' VERT. SCALE 1" = 2'