

**BID RESULTS**

City of Riverside  
Finance Dept./Purchasing

<b>Due Date</b>	1/13/2016	<b>Bid No.</b>	7354
<b>Before</b>	2:00pm	<b>Estimate</b>	\$7,698,994.25

<b>Bid Description</b>		
<b>2015/2016 Arterial and Minor Streets Maintenance</b>		
<b>Apparent Low Bidder</b>	<b>Location</b>	<b>Bid Amount</b>
All American Asphalt	Corona, CA	\$7,330,678.00

<b>Additional Bid Responses</b>	<b>Location</b>	<b>Bid Amount</b>
Sequel Contractors, Inc.	Santa Fe Springs, CA	\$7,352,224.75
Hardy & Harper, Inc.	Santa Ana, CA	\$7,447,000.00
Griffith Company	Montclair, CA	\$7,678,460.50
R.J. Noble Company	Orange, CA	\$7,920,147.45
EBS General Engineering, Inc.	Corona, CA	\$8,462,500.00
Excel Paving Company	Long Beach, CA	\$9,079,375.00

<b>Non-Responsive</b>
N/A

# BID RESULTS

City of Riverside  
Finance Dept./Purchasing

Due Date	1/13/2016	Bid No.	7354
Before	2:00pm	Estimate	\$7,698,994.25

## Bid Description

2015/2016 Arterial and Minor Streets Maintenance

### Bidder

All American Asphalt

Item No.	Item Description	Qty	Unit	Unit Price	Ext. Price
<b>Incidental Items</b>					
1	<b>Note:</b> All items subject to any special notes or footnotes appearing on this Engineer's estimate included with the bid documents.	...	...	...	...
2	<b>Note:</b> The Contract lump sum or unit price for each Contract Bid Item shall include full compensation for all labor, materials, tools, taxes, profit, overhead, incidentals and appurtenant work necessary for performing and completing the work of the Contract Bid Item as required by the Project Plans, Specifications, Special Provisions and other Contract Documents. Such compensation shall also include or take into consideration any additional provisions or conditions specifically stated immediately following the Contract Bid Item.	...	...	...	...
3	<b>Note:</b> In the absence of a specific bid item or specific payment provisions for any portion of the work required by the Contract Documents, the bidder shall include the bidder's compensation for that portion of the Contract work in the Contract unit price(s) and/or lump sum price(s) of the bid item(s) that require such work, or are closely related to such work. Therefore, no separate or additional payment will be made to the Contractor for any such work on the premise that such work lacks specific bid item(s) or specific payment provisions.	...	...	...	...
4	<b>Note:</b> "(P)" adjacent to a Contract bid item designates a "Partial Pay Item" per Section 9-3.2 of the Special Provisions.	...	...	...	...
5	<b>Note:</b> "(F)" adjacent to a Contract bid item designates a Final Pay Quantity per Section 9-3.2.1 of the Special Provisions.	...	...	...	...
6	<b>Note:</b> "(S)" adjacent to a Contract bid item designates a "Specialty Item" per Section 2-3.2 of the Special Provisions.	...	...	...	...
7	<b>Mobilization for Arterial Streets &amp; Exhibit G (Bid Items 11, 15, and 19 thru 80), (P)</b>	1	LS	\$87,400.00	\$87,400.00
8	<b>Mobilization for Minor Streets (Bid Items 12, 16, and 81 thru 115), (P)</b>	1	LS	\$63,000.00	\$63,000.00
9	<b>Mobilization for Jurupa Avenue Storm Drain (Bid Items 13, 17, and 116 thru 118), (P)</b>	1	LS	\$8,425.00	\$8,425.00
10	<b>Mobilization for Exhibit H (Bid Items 14, 18, and 119 thru 127), (P)</b>	1	LS	\$8,710.00	\$8,710.00
11	<b>Water Pollution Control for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P)</b>	1	LS	\$27,700.00	\$27,700.00
12	<b>Water Pollution Control for Minor Streets (Bid Items 81 thru 115), (P)</b>	1	LS	\$27,600.00	\$27,600.00
13	<b>Water Pollution Control for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P)</b>	1	LS	\$2,050.00	\$2,050.00
14	<b>Water Pollution Control for Exhibit H (Bid Items 119 thru 127), (P)</b>	1	LS	\$4,100.00	\$4,100.00
15	<b>Traffic Control and Access for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$125,400.00	\$125,400.00
16	<b>Traffic Control and Access for Minor Streets (Bid Items 81 thru 115), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$133,360.00	\$133,360.00

17	<b>Traffic Control and Access for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$25,200.00	\$25,200.00
18	<b>Traffic Control and Access for Exhibit H (Bid Items 119 thru 127), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$12,600.00	\$12,600.00
<b>Sub-Total: Incidental Items</b>					\$525,545.00
<b>Arterial Street Maintenance (R-4336 and Exhibit G)</b>					
19	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,500	CY	\$30.00	\$75,000.00
20	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	1,300	CY	\$37.00	\$48,100.00
21	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,000	TON	\$68.00	\$136,000.00
22	<b>Unclassified Excavation for W. La Cadena Drive, (F).</b> (Includes approximately 100 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	120	CY	\$153.00	\$18,360.00
23	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b>	3,500	LF	\$1.50	\$5,250.00
24	<b>Cold Milling - Type CM2 (Depth Varies Per Plan).</b>	730,000	SF	\$0.17	\$124,100.00
25	<b>Cold Milling - Type CM3 (Full Depth).</b>	15,000	SF	\$0.50	\$7,500.00
26	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans. Includes median removals when required.)	7,200	TON	\$59.00	\$424,800.00
27	<b>Asphalt Rubber Hot Mix - Gap Graded (ARHM-GG) (0.12' min.) Overlay</b>	7,500	TON	\$77.00	\$577,500.00
28	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F).</b> (Applies to all surface treatment locations regardless if a median exists or not.)	14,000	LF	\$2.14	\$29,960.00
29	<b>Adjust Manhole Cover to Grade.</b> (Includes Electric, Telephone, Sewer, and Storm Drain manhole covers, and grate inlets.)	90	EA	\$357.00	\$32,130.00
30	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade.</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	100	EA	\$255.00	\$25,500.00
31	<b>Adjust Electric Manhole Vault Frame to Grade.</b> (Includes any adjustment/protection necessary for top to sit flush or 1/4" above finished grade. Includes proper electrical licensing.)	9	EA	\$3,000.00	\$27,000.00
32	<b>Concrete Curb and Gutter per City Std. 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on the plans.)	3,750	LF	\$46.00	\$172,500.00
33	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	210	LF	\$86.00	\$18,060.00
34	<b>Cobblestone Curb and Gutter per Part 10 of the Special Provisions</b>	500	LF	\$60.00	\$30,000.00
35	<b>Concrete Retaining Curb. (0"-18")</b>	550	LF	\$18.00	\$9,900.00
36	<b>Construct AC Berm per City Std. 250.</b> (Includes W. La Cadena Avenue and Central Avenue in locations as indicated on the plans or if necessary. Also includes hand forming where necessary.)	600	LF	\$4.00	\$2,400.00
37	<b>Concrete Cross Gutter per City Std. 220.</b> (Includes all modifications as indicated.)	5,000	SF	\$13.00	\$65,000.00
38	<b>Concrete Driveway per City Std. 302.</b> (Includes all modifications as indicated.)	10,000	SF	\$9.00	\$90,000.00

39	<b>PCC Pedestrian Ramp per City Std. 304 or Caltrans Standard Plan A88A.</b> (Type per plan, includes any modifications as necessary.)	65	EA	\$3,000.00	\$195,000.00
40	<b>PCC Sidewalk per City Std. 325.</b> (Includes parkway slope grading in conformance with City Std. 325.)	25,500	SF	\$6.10	\$155,550.00
41	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	550	SF	\$9.00	\$4,950.00
42	<b>R&amp;R Catch Basin Apron Only, per City Std. 405</b>	1	EA	\$1,300.00	\$1,300.00
43	<b>Parkway Drain per City Std. 410</b>	2	EA	\$3,700.00	\$7,400.00
44	<b>Concrete Pavement Section on Rivera Street</b>	1,150	SF	\$12.00	\$13,800.00
45	<b>Concrete Bus Pad per Detail in Special Provisions</b>	14	EA	\$18,100.00	\$253,400.00
46	<b>3.5" Thick Concrete Median</b>	25	SF	\$145.00	\$3,625.00
47	<b>Decorative White Rock for Tree Wells on Central Avenue.</b> (Includes clearing tree wells of dirt, debris, stumps, and tripping hazards.)	10	CY	\$200.00	\$2,000.00
48	<b>Crushed Rock Permeable Tree Well, (S).</b> (Includes training, all subsurface preparation, geogrids, aggregates, resins, and installation. Well sizes range from 16 SF to 54 SF. Total square footage for selected tree wells is 1600 SF. Product type must match Rockpave FlowStone "Desert Rose" from Exhibit C in Part 10 of the Special Provisions, or City approved equal.)	39	EA	\$1,450.00	\$56,550.00
49	<b>Exhibit G - Unclassified Excavation for Slope Restoration at Canyon Ridge Drive and Van Buren Blvd, (F).</b> (Includes approximately 50 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	800	CY	\$25.00	\$20,000.00
50	<b>Exhibit G - Import Fill, (F).</b> (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	375	CY	\$33.00	\$12,375.00
51	<b>Exhibit G - White Vinyl Fence.</b> (Type and color shall match existing. Includes all work to connect to existing fence as indicated on Exhibit G in Part 10 of the Special Provisions.)	25	LF	\$77.00	\$1,925.00
52	<b>Exhibit G - Hydroseed.</b> (Includes 365 days of hydroseed establishment.)	5,000	SF	\$2.50	\$12,500.00
<b>Sub-Total: Arterial Street Maintenance (R-4346 and Exhibit G)</b>					<b>\$2,659,435.00</b>
<b>Arterial Traffic Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					
53	<b>Install Sign (No Post), (S)</b>	3	EA	\$128.00	\$384.00
54	<b>Install Sign (One Post), (S)</b>	22	EA	\$194.00	\$4,268.00
55	<b>Install Street Name Sign, (S)</b>	21	EA	\$306.00	\$6,426.00
56	<b>Remove Sign, (S)</b>	29	EA	\$66.00	\$1,914.00
57	<b>4" Dashed White Stripe (Thermo) - Detail 9 w/ RPM(s), (S)</b>	21,020	LF	\$0.30	\$6,306.00
58	<b>Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)</b>	10,010	LF	\$0.70	\$7,007.00
59	<b>Detail 26 - (RPM's)</b>	400	LF	\$1.00	\$400.00
60	<b>4" Solid White Stripe (Thermo) - Detail 27B, (S)</b>	2,840	LF	\$0.40	\$1,136.00
61	<b>Double Yellow Median Island Stripe (Thermo) - Detail 29 w/ RPM(s), (S)</b>	1,210	LF	\$1.20	\$1,452.00
62	<b>Two Way Left Trun Stripe (Thermo) - Detail 32 w/ RPM(s), (S)</b>	2,765	LF	\$1.40	\$3,871.00
63	<b>Exit Ramp Neutral Area (Thermo) - Detail 36 w/ RPMs, (S)</b>	345	LF	\$1.20	\$414.00
64	<b>8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)</b>	1,925	LF	\$0.90	\$1,732.50
65	<b>8" Solid White Stripe (Thermo) - Detail 38A, (S)</b>	200	LF	\$0.92	\$184.00
66	<b>8" Solid White Stripe (Thermo) - Detail 39, (S)</b>	16,435	LF	\$0.40	\$6,574.00
67	<b>8" Solid White Stripe (Thermo) - Detail 39A, (S)</b>	2,620	LF	\$0.40	\$1,048.00
68	<b>4" Dashed White Stripe (Thermo) - Detail 40, (S)</b>	665	LF	\$0.40	\$266.00
69	<b>4" Solid Stripe (Thermo), (S)</b>	3,110	LF	\$0.40	\$1,244.00
70	<b>6" Solid Stripe (Thermo), (S)</b>	755	LF	\$1.00	\$755.00
71	<b>12" Solid Stripe (Thermo), (S)</b>	5,240	SF	\$1.30	\$6,812.00

72	Pavement Markings (Thermo), (S)	3,090	SF	\$2.50	\$7,725.00
73	Paint Median Nose w/ RPM(s), (S)	3	EA	\$136.00	\$408.00
74	Paint Curb (Red, White, or Yellow), (S)	285	LF	\$2.00	\$570.00
75	Type "C" Detector Loop, (S)	6	EA	\$765.00	\$4,590.00
76	Type "D" Detector Loop, (S)	51	EA	\$240.00	\$12,240.00
77	Type "E" Detector Loop, (S)	117	EA	\$214.00	\$25,038.00
78	SC - Splice new to existing conductors, (S)	33	EA	\$20.00	\$660.00
79	DLC - Detector Loop Cable, (S)	2,895	LF	\$2.20	\$6,369.00
80	2-Channel Detector Card, (S)	13	EA	\$286.00	\$3,718.00
Sub-Total: Arterial Street Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)					\$113,511.50
<b>Minor Street Maintenance And Traffic Improvements (R-4346 and R-4351)</b>					
81	Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth). (Includes variable grind when indicated)	510	LF	\$2.10	\$1,071.00
82	Cold Milling, Type CM2 (Depth Varies Per Plan) (Includes variable grind when indicated)	290,000	SF	\$0.20	\$58,000.00
83	Cold Milling, Type CM3 (Full Depth)	52,000	SF	\$0.43	\$22,360.00
84	Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F) (Includes all areas to receive Slurry Seal, ARAM treatment, and Cold Milling Type CM1/CM2.)	101,000	LF	\$2.00	\$202,000.00
85	Crushed Aggregate Base, (F)	1,070	CY	\$43.00	\$46,010.00
86	Asphalt Pavement - DGAC (Includes all new paving and replacement paving in areas indicated on plans and slot patches.)	4,010	TONS	\$61.00	\$244,610.00
87	Construct Asphalt Rubber Aggregate Membrane (ARAM) (S)	2,980,000	SF	\$0.41	\$1,221,800.00
88	Construct Slurry Seal, Type II	2,980,000	SF	\$0.13	\$387,400.00
89	Removal of Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	1,500	CY	\$30.00	\$45,000.00
90	Replacement Base for Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	500	CY	\$37.00	\$18,500.00
91	Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	250	TN	\$68.00	\$17,000.00
92	Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade (Includes cleaning and painting all facilities and installing city furnished material as specified.)	300	EA	\$250.00	\$75,000.00
93	Adjust Manhole to Grade (Includes Electric, Water, Sewer, and Storm Drain manhole covers)	385	EA	\$357.00	\$137,445.00
94	Concrete Curb and Gutter per City Std 200. (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on plans.)	2,600	LF	\$46.00	\$119,600.00
95	Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions	1,400	LF	\$80.00	\$112,000.00
96	Concrete Cross Gutter per Std 220 (Includes ribbon gutters and all modifications as indicated.)	4,000	SF	\$13.00	\$52,000.00
97	Concrete Driveway per City Std 302. (Includes all modifications as indicated.)	1,200	SF	\$9.00	\$10,800.00
98	PCC Pedstrian Ramp per City Std 304. (Type per plan, includes any modifications as necessary.)	275	EA	\$3,000.00	\$825,000.00
99	PCC Pedstrian Ramp per City Std 304, Type VII	1,450	SF	\$7.10	\$10,295.00
100	PCC Sidewalk per City Std 325 (Includes parkway slope grading in conformance with the plans and the Standard 325. Also includes sidewalk of 6" thickness where indicated or required for the driveway approach. Includes furnishing and installing traffic rated boxes and lids when indicated)	35,000	SF	\$6.10	\$213,500.00
101	PCC Sidewalk per City Std 325, Modified (6" Thick)	1,200	SF	\$9.00	\$10,800.00
102	Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)	8,835	LF	\$0.70	\$6,184.50

103	4" Solid White Stripe (Thermo) - Detail 27B, (S)	595	LF	\$0.40	\$238.00
104	8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)	65	LF	\$0.90	\$58.50
105	12" Solid Stripe White or Yellow (Thermo), (S)	6,150	SF	\$1.30	\$7,995.00
106	Pavement Legends / Markings (Thermo), (S)	4,475	SF	\$2.50	\$11,187.50
107	Type "G" Markers, (S)	17	EA	\$5.00	\$85.00
108	Type "D" Detector Loop, (S)	9	EA	\$240.00	\$2,160.00
109	Remove Sign (No Post), (S)	31	EA	\$41.00	\$1,271.00
110	Remove Sign (One Post), (S)	193	EA	\$66.00	\$12,738.00
111	Install Sign (No Post), (S)	37	EA	\$123.00	\$4,551.00
112	Install Sign (One Post), (S)	126	EA	\$194.00	\$24,444.00
113	Install Street Name Sign, (S)	123	EA	\$305.00	\$37,515.00
114	Relocate Sign (No Post), (S)	22	EA	\$51.00	\$1,122.00
115	Relocate Sign (One Post), (S)	2	EA	\$128.00	\$256.00
<b>Sub-Total: Minor Street Maintenance and Traffic Improvements (R-4346 and R-4351)</b>					<b>\$3,939,996.50</b>
<b>Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					
116	Furnish and Install 18" RCP Pipe. (Includes pre and post inspection video requirements, PWS connection at the existing RCB, and all requirements as described in the Special Provisions.)	66	LF	\$360.00	\$23,760.00
117	Construct Catch Basin per City Std 405, W=8'	1	EA	\$9,400.00	\$9,400.00
118	Construct Concrete Sidewalk per City Std 325	325	SF	\$9.80	\$3,185.00
<b>Sub-Total: Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					<b>\$36,345.00</b>
<b>Fountain Demolition and Landscape Improvements (Exhibit H)</b>					
119	Concrete / Cobble Fountain Structure Demolition (Includes all labor and equipment for demolition and proper disposal)	1	LS	\$26,700.00	\$26,700.00
120	Soil Preparation/Fine Grading	2,200	SF	\$1.30	\$2,860.00
121	Import Fill, (F). (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	175	CY	\$63.00	\$11,025.00
122	Top Soil, (F)	20	CY	\$66.00	\$1,320.00
123	Wood Mulch (2" Layer)	2,200	SF	\$0.90	\$1,980.00
124	Sod	120	SF	\$2.50	\$300.00
125	1 Gallon Drought Tolerant Plantings	130	EA	\$12.00	\$1,560.00
126	Design, Furnish & Install/Modify Irrigation System	1	LS	\$7,100.00	\$7,100.00
127	NDS atrium grate and cleanout box, 3" pvc pipes, Curb outlet, and coring.	1	LS	\$3,000.00	\$3,000.00
<b>Sub-Total: Fountain Demolition and Landscape Improvements (Exhibit H)</b>					<b>\$55,845.00</b>
					<b>Bid Total</b>
					<b>\$7,330,678.00</b>

<b>Subcontractor Information</b>			
<b>Subcontractor Name</b>	<b>Location</b>	<b>Portion</b>	<b>Amount</b>
American Pavement Systems	Modesto, CA	Portion of ARAM	\$334,920.00
Cal Stripe Inc.	Colton, CA	Signing/Striping/Marking	\$165,076.00
Kato Landscape	Fountain Valley, CA	Landscape/Irrigation	\$84,855.00
California Professional	La Puente, CA	Loops	\$53,549.50

**BID RESULTS**

City of Riverside  
Finance Dept./Purchasing

<b>Due Date</b>	1/13/2016	<b>Bid No.</b>	7354
<b>Before</b>	2:00pm	<b>Estimate</b>	\$7,698,994.25

**Bid Description**

2015/2016 Arterial and Minor Streets Maintenance

**Bidder**

Sequel Contractors, Inc.

Item No.	Item Description	Qty	Unit	Unit Price	Ext. Price
<b>Incidental Items</b>					
1	<b>Note:</b> All items subject to any special notes or footnotes appearing on this Engineer's estimate included with the bid documents.	...	...	...	...
2	<b>Note:</b> The Contract lump sum or unit price for each Contract Bid Item shall include full compensation for all labor, materials, tools, taxes, profit, overhead, incidentals and appurtenant work necessary for performing and completing the work of the Contract Bid Item as required by the Project Plans, Specifications, Special Provisions and other Contract Documents. Such compensation shall also include or take into consideration any additional provisions or conditions specifically stated immediately following the Contract Bid Item.	...	...	...	...
3	<b>Note:</b> In the absence of a specific bid item or specific payment provisions for any portion of the work required by the Contract Documents, the bidder shall include the bidder's compensation for that portion of the Contract work in the Contract unit price(s) and/or lump sum price(s) of the bid item(s) that require such work, or are closely related to such work. Therefore, no separate or additional payment will be made to the Contractor for any such work on the premise that such work lacks specific bid item(s) or specific payment provisions.	...	...	...	...
4	<b>Note:</b> "(P)" adjacent to a Contract bid item designates a "Partial Pay Item" per Section 9-3.2 of the Special Provisions.	...	...	...	...
5	<b>Note:</b> "(F)" adjacent to a Contract bid item designates a Final Pay Quantity per Section 9-3.2.1 of the Special Provisions.	...	...	...	...
6	<b>Note:</b> "(S)" adjacent to a Contract bid item designates a "Specialty Item" per Section 2-3.2 of the Special Provisions.	...	...	...	...
7	<b>Mobilization for Arterial Streets &amp; Exhibit G (Bid Items 11, 15, and 19 thru 80), (P)</b>	1	LS	\$100,000.00	\$100,000.00
8	<b>Mobilization for Minor Streets (Bid Items 12, 16, and 81 thru 115), (P)</b>	1	LS	\$150,000.00	\$150,000.00
9	<b>Mobilization for Jurupa Avenue Storm Drain (Bid Items 13, 17, and 116 thru 118), (P)</b>	1	LS	\$2,000.00	\$2,000.00
10	<b>Mobilization for Exhibit H (Bid Items 14, 18, and 119 thru 127), (P)</b>	1	LS	\$2,000.00	\$2,000.00
11	<b>Water Pollution Control for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P)</b>	1	LS	\$10,000.00	\$10,000.00
12	<b>Water Pollution Control for Minor Streets (Bid Items 81 thru 115), (P)</b>	1	LS	\$10,000.00	\$10,000.00
13	<b>Water Pollution Control for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P)</b>	1	LS	\$2,000.00	\$2,000.00
14	<b>Water Pollution Control for Exhibit H (Bid Items 119 thru 127), (P)</b>	1	LS	\$2,000.00	\$2,000.00
15	<b>Traffic Control and Access for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$150,000.00	\$150,000.00
16	<b>Traffic Control and Access for Minor Streets (Bid Items 81 thru 115), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$117,500.00	\$117,500.00

17	<b>Traffic Control and Access for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$6,000.00	\$6,000.00
18	<b>Traffic Control and Access for Exhibit H (Bid Items 119 thru 127), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$3,000.00	\$3,000.00
<b>Sub-Total: Incidental Items</b>					\$554,500.00
<b>Arterial Street Maintenance (R-4336 and Exhibit G)</b>					
19	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,500	CY	\$40.00	\$100,000.00
20	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	1,300	CY	\$30.00	\$39,000.00
21	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,000	TON	\$56.00	\$112,000.00
22	<b>Unclassified Excavation for W. La Cadena Drive, (F).</b> (Includes approximately 100 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	120	CY	\$100.00	\$12,000.00
23	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b>	3,500	LF	\$1.20	\$4,200.00
24	<b>Cold Milling - Type CM2 (Depth Varies Per Plan).</b>	730,000	SF	\$0.20	\$146,000.00
25	<b>Cold Milling - Type CM3 (Full Depth).</b>	15,000	SF	\$0.50	\$7,500.00
26	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans. Includes median removals when required.)	7,200	TON	\$60.00	\$432,000.00
27	<b>Asphalt Rubber Hot Mix - Gap Graded (ARHM-GG) (0.12' min.) Overlay</b>	7,500	TON	\$82.00	\$615,000.00
28	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F).</b> (Applies to all surface treatment locations regardless if a median exists or not.)	14,000	LF	\$2.00	\$28,000.00
29	<b>Adjust Manhole Cover to Grade.</b> (Includes Electric, Telephone, Sewer, and Storm Drain manhole covers, and grate inlets.)	90	EA	\$500.00	\$45,000.00
30	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade.</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	100	EA	\$500.00	\$50,000.00
31	<b>Adjust Electric Manhole Vault Frame to Grade.</b> (Includes any adjustment/protection necessary for top to sit flush or 1/4" above finished grade. Includes proper electrical licensing.)	9	EA	\$4,000.00	\$36,000.00
32	<b>Concrete Curb and Gutter per City Std. 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on the plans.)	3,750	LF	\$39.00	\$146,250.00
33	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	210	LF	\$70.00	\$14,700.00
34	<b>Cobblestone Curb and Gutter per Part 10 of the Special Provisions</b>	500	LF	\$80.00	\$40,000.00
35	<b>Concrete Retaining Curb. (0"-18")</b>	550	LF	\$17.00	\$9,350.00
36	<b>Construct AC Berm per City Std. 250.</b> (Includes W. La Cadena Avenue and Central Avenue in locations as indicated on the plans or if necessary. Also includes hand forming where necessary.)	600	LF	\$7.00	\$4,200.00
37	<b>Concrete Cross Gutter per City Std. 220.</b> (Includes all modifications as indicated.)	5,000	SF	\$11.00	\$55,000.00
38	<b>Concrete Driveway per City Std. 302.</b> (Includes all modifications as indicated.)	10,000	SF	\$8.00	\$80,000.00
39	<b>PCC Pedestrian Ramp per City Std. 304 or Caltrans Standard Plan A88A.</b> (Type per plan, includes any modifications as necessary.)	65	EA	\$3,000.00	\$195,000.00

40	<b>PCC Sidewalk per City Std. 325.</b> (Includes parkway slope grading in conformance with City Std. 325.)	25,500	SF	\$6.00	\$153,000.00
41	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	550	SF	\$8.00	\$4,400.00
42	<b>R&amp;R Catch Basin Apron Only, per City Std. 405</b>	1	EA	\$5,000.00	\$5,000.00
43	<b>Parkway Drain per City Std. 410</b>	2	EA	\$5,000.00	\$10,000.00
44	<b>Concrete Pavement Section on Rivera Street</b>	1,150	SF	\$20.00	\$23,000.00
45	<b>Concrete Bus Pad per Detail in Special Provisions</b>	14	EA	\$15,000.00	\$210,000.00
46	<b>3.5" Thick Concrete Median</b>	25	SF	\$100.00	\$2,500.00
47	<b>Decorative White Rock for Tree Wells on Central Avenue.</b> (Includes clearing tree wells of dirt, debris, stumps, and tripping hazards.)	10	CY	\$1,200.00	\$12,000.00
48	<b>Crushed Rock Permeable Tree Well, (S).</b> (Includes training, all subsurface preparation, geogrids, aggregates, resins, and installation. Well sizes range from 16 SF to 54 SF. Total square footage for selected tree wells is 1600 SF. Product type must match Rockpave FlowStone "Desert Rose" from Exhibit C in Part 10 of the Special Provisions, or City approved equal.)	39	EA	\$1,000.00	\$39,000.00
49	<b>Exhibit G - Unclassified Excavation for Slope Restoration at Canyon Ridge Drive and Van Buren Blvd, (F).</b> (Includes approximately 50 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	800	CY	\$25.00	\$20,000.00
50	<b>Exhibit G - Import Fill, (F).</b> (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	375	CY	\$75.00	\$28,125.00
51	<b>Exhibit G - White Vinyl Fence.</b> (Type and color shall match existing. Includes all work to connect to existing fence as indicated on Exhibit G in Part 10 of the Special Provisions.)	25	LF	\$200.00	\$5,000.00
52	<b>Exhibit G - Hydroseed.</b> (Includes 365 days of hydroseed establishment.)	5,000	SF	\$1.00	\$5,000.00
<b>Sub-Total: Arterial Street Maintenance (R-4346 and Exhibit G)</b>					<b>\$2,688,225.00</b>
<b>Arterial Traffic Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					
53	<b>Install Sign (No Post), (S)</b>	3	EA	\$115.00	\$345.00
54	<b>Install Sign (One Post), (S)</b>	22	EA	\$170.00	\$3,740.00
55	<b>Install Street Name Sign, (S)</b>	21	EA	\$350.00	\$7,350.00
56	<b>Remove Sign, (S)</b>	29	EA	\$35.00	\$1,015.00
57	<b>4" Dashed White Stripe (Thermo) - Detail 9 w/ RPM(s), (S)</b>	21,020	LF	\$0.40	\$8,408.00
58	<b>Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)</b>	10,010	LF	\$1.15	\$11,511.50
59	<b>Detail 26 - (RPM's)</b>	400	LF	\$0.25	\$100.00
60	<b>4" Solid White Stripe (Thermo) - Detail 27B, (S)</b>	2,840	LF	\$0.60	\$1,704.00
61	<b>Double Yellow Median Island Stripe (Thermo) - Detail 29 w/ RPM(s), (S)</b>	1,210	LF	\$1.15	\$1,391.50
62	<b>Two Way Left Trun Stripe (Thermo) - Detail 32 w/ RPM(s), (S)</b>	2,765	LF	\$2.50	\$6,912.50
63	<b>Exit Ramp Neutral Area (Thermo) - Detail 36 w/ RPMs, (S)</b>	345	LF	\$1.40	\$483.00
64	<b>8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)</b>	1,925	LF	\$1.40	\$2,695.00
65	<b>8" Solid White Stripe (Thermo) - Detail 38A, (S)</b>	200	LF	\$1.50	\$300.00
66	<b>8" Solid White Stripe (Thermo) - Detail 39, (S)</b>	16,435	LF	\$0.90	\$14,791.50
67	<b>8" Solid White Stripe (Thermo) - Detail 39A, (S)</b>	2,620	LF	\$1.00	\$2,620.00
68	<b>4" Dashed White Stripe (Thermo) - Detail 40, (S)</b>	665	LF	\$1.00	\$665.00
69	<b>4" Solid Stripe (Thermo), (S)</b>	3,110	LF	\$1.20	\$3,732.00
70	<b>6" Solid Stripe (Thermo), (S)</b>	755	LF	\$1.50	\$1,132.50
71	<b>12" Solid Stripe (Thermo), (S)</b>	5,240	SF	\$2.00	\$10,480.00
72	<b>Pavement Markings (Thermo), (S)</b>	3,090	SF	\$5.00	\$15,450.00
73	<b>Paint Median Nose w/ RPM(s), (S)</b>	3	EA	\$60.00	\$180.00

74	Paint Curb (Red, White, or Yellow), (S)	285	LF	\$3.00	\$855.00
75	Type "C" Detector Loop, (S)	6	EA	\$400.00	\$2,400.00
76	Type "D" Detector Loop, (S)	51	EA	\$200.00	\$10,200.00
77	Type "E" Detector Loop, (S)	117	EA	\$200.00	\$23,400.00
78	SC - Splice new to existing conductors, (S)	33	EA	\$200.00	\$6,600.00
79	DLC - Detector Loop Cable, (S)	2,895	LF	\$4.00	\$11,580.00
80	2-Channel Detector Card, (S)	13	EA	\$300.00	\$3,900.00
Sub-Total: Arterial Street Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)					\$153,941.50
<b>Minor Street Maintenance And Traffic Improvements (R-4346 and R-4351)</b>					
81	Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth). (Includes variable grind when indicated)	510	LF	\$3.00	\$1,530.00
82	Cold Milling, Type CM2 (Depth Varies Per Plan) (Includes variable grind when indicated)	290,000	SF	\$0.25	\$72,500.00
83	Cold Milling, Type CM3 (Full Depth)	52,000	SF	\$0.40	\$20,800.00
84	Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F) (Includes all areas to receive Slurry Seal, ARAM treatment, and Cold Milling Type CM1/CM2.)	101,000	LF	\$1.50	\$151,500.00
85	Crushed Aggregate Base, (F)	1,070	CY	\$35.00	\$37,450.00
86	Asphalt Pavement - DGAC (Includes all new paving and replacement paving in areas indicated on plans and slot patches.)	4,010	TONS	\$58.00	\$232,580.00
87	Construct Asphalt Rubber Aggregate Membrane (ARAM) (S)	2,980,000	SF	\$0.40	\$1,192,000.00
88	Construct Slurry Seal, Type II	2,980,000	SF	\$0.15	\$447,000.00
89	Removal of Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	1,500	CY	\$40.00	\$60,000.00
90	Replacement Base for Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	500	CY	\$30.00	\$15,000.00
91	Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	250	TN	\$56.00	\$14,000.00
92	Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade (Includes cleaning and painting all facilities and installing city furnished material as specified.)	300	EA	\$250.00	\$75,000.00
93	Adjust Manhole to Grade (Includes Electric, Water, Sewer, and Storm Drain manhole covers)	385	EA	\$250.00	\$96,250.00
94	Concrete Curb and Gutter per City Std 200. (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on plans.)	2,600	LF	\$35.00	\$91,000.00
95	Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions	1,400	LF	\$70.00	\$98,000.00
96	Concrete Cross Gutter per Std 220 (Includes ribbon gutters and all modifications as indicated.)	4,000	SF	\$11.00	\$44,000.00
97	Concrete Driveway per City Std 302. (Includes all modifications as indicated.)	1,200	SF	\$8.00	\$9,600.00
98	PCC Pedstrian Ramp per City Std 304. (Type per plan, includes any modifications as necessary.)	275	EA	\$3,000.00	\$825,000.00
99	PCC Pedstrian Ramp per City Std 304, Type VII	1,450	SF	\$30.00	\$43,500.00
100	PCC Sidewalk per City Std 325 (Includes parkway slope grading in conformance with the plans and the Standard 325. Also includes sidewalk of 6" thickness where indicated or required for the driveway approach. Includes furnishing and installing traffic rated boxes and lids when indicated)	35,000	SF	\$5.90	\$206,500.00
101	PCC Sidewalk per City Std 325, Modified (6" Thick)	1,200	SF	\$8.00	\$9,600.00
102	Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)	8,835	LF	\$1.15	\$10,160.25
103	4" Solid White Stripe (Thermo) - Detail 27B, (S)	595	LF	\$0.60	\$357.00
104	8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)	65	LF	\$1.40	\$91.00
105	12" Solid Stripe White or Yellow (Thermo), (S)	6,150	SF	\$2.00	\$12,300.00

106	Pavement Legends / Markings (Thermo), (S)	4,475	SF	\$5.00	\$22,375.00
107	Type "G" Markers, (S)	17	EA	\$5.00	\$85.00
108	Type "D" Detector Loop, (S)	9	EA	\$300.00	\$2,700.00
109	Remove Sign (No Post), (S)	31	EA	\$35.00	\$1,085.00
110	Remove Sign (One Post), (S)	193	EA	\$75.00	\$14,475.00
111	Install Sign (No Post), (S)	37	EA	\$115.00	\$4,255.00
112	Install Sign (One Post), (S)	126	EA	\$170.00	\$21,420.00
113	Install Street Name Sign, (S)	123	EA	\$350.00	\$43,050.00
114	Relocate Sign (No Post), (S)	22	EA	\$70.00	\$1,540.00
115	Relocate Sign (One Post), (S)	2	EA	\$100.00	\$200.00
<b>Sub-Total: Minor Street Maintenance and Traffic Improvements (R-4346 and R-4351)</b>					<b>\$3,876,903.25</b>
<b>Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					
116	Furnish and Install 18" RCP Pipe. (Includes pre and post inspection video requirements, PWS connection at the existing RCB, and all requirements as described in the Special Provisions.)	66	LF	\$350.00	\$23,100.00
117	Construct Catch Basin per City Std 405, W=8'	1	EA	\$8,000.00	\$8,000.00
118	Construct Concrete Sidewalk per City Std 325	325	SF	\$10.00	\$3,250.00
<b>Sub-Total: Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					<b>\$34,350.00</b>
<b>Fountain Demolition and Landscape Improvements (Exhibit H)</b>					
119	Concrete / Cobble Fountain Structure Demolition (Includes all labor and equipment for demolition and proper disposal)	1	LS	\$25,000.00	\$25,000.00
120	Soil Preparation/Fine Grading	2,200	SF	\$1.00	\$2,200.00
121	Import Fill, (F). (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	175	CY	\$25.00	\$4,375.00
122	Top Soil, (F)	20	CY	\$75.00	\$1,500.00
123	Wood Mulch (2" Layer)	2,200	SF	\$0.50	\$1,100.00
124	Sod	120	SF	\$1.50	\$180.00
125	1 Gallon Drought Tolerant Plantings	130	EA	\$15.00	\$1,950.00
126	Design, Furnish & Install/Modify Irrigation System	1	LS	\$5,000.00	\$5,000.00
127	NDS atrium grate and cleanout box, 3" pvc pipes, Curb outlet, and coring.	1	LS	\$3,000.00	\$3,000.00
<b>Sub-Total: Fountain Demolition and Landscape Improvements (Exhibit H)</b>					<b>\$44,305.00</b>
					<b>Bid Total</b>
					<b>\$7,352,224.75</b>

<b>Subcontractor Information</b>			
<b>Subcontractor Name</b>	<b>Location</b>	<b>Portion</b>	<b>Amount</b>
CL Concrete	Azusa, CA	PCC Pow	\$1,320,000.00
American Pavement Systems	Modesto, CA	ARAM	\$1,311,000.00
All American	Corona, CA	Slurry Seal	\$447,000.00
Cal Stripe	Colton, CA	Stripe	\$165,000.00
EBS	Corona, CA	Adjustments	\$354,000.00
Global	Garden Grove, CA	Loops/Crack Seal	\$295,000.00

All American	Corona, CA	Cold Milling	\$216,040.00
--------------	------------	--------------	--------------

# BID RESULTS

City of Riverside  
Finance Dept./Purchasing

Due Date	1/13/2016	Bid No.	7354
Before	2:00pm	Estimate	\$7,698,994.25

## Bid Description

2015/2016 Arterial and Minor Streets Maintenance

### Bidder

Hardy & Harper, Inc.

Item No.	Item Description	Qty	Unit	Unit Price	Ext. Price
<b>Incidental Items</b>					
1	<b>Note:</b> All items subject to any special notes or footnotes appearing on this Engineer's estimate included with the bid documents.	...	...	...	...
2	<b>Note:</b> The Contract lump sum or unit price for each Contract Bid Item shall include full compensation for all labor, materials, tools, taxes, profit, overhead, incidentals and appurtenant work necessary for performing and completing the work of the Contract Bid Item as required by the Project Plans, Specifications, Special Provisions and other Contract Documents. Such compensation shall also include or take into consideration any additional provisions or conditions specifically stated immediately following the Contract Bid Item.	...	...	...	...
3	<b>Note:</b> In the absence of a specific bid item or specific payment provisions for any portion of the work required by the Contract Documents, the bidder shall include the bidder's compensation for that portion of the Contract work in the Contract unit price(s) and/or lump sum price(s) of the bid item(s) that require such work, or are closely related to such work. Therefore, no separate or additional payment will be made to the Contractor for any such work on the premise that such work lacks specific bid item(s) or specific payment provisions.	...	...	...	...
4	<b>Note:</b> "(P)" adjacent to a Contract bid item designates a "Partial Pay Item" per Section 9-3.2 of the Special Provisions.	...	...	...	...
5	<b>Note:</b> "(F)" adjacent to a Contract bid item designates a Final Pay Quantity per Section 9-3.2.1 of the Special Provisions.	...	...	...	...
6	<b>Note:</b> "(S)" adjacent to a Contract bid item designates a "Specialty Item" per Section 2-3.2 of the Special Provisions.	...	...	...	...
7	<b>Mobilization for Arterial Streets &amp; Exhibit G (Bid Items 11, 15, and 19 thru 80), (P)</b>	1	LS	\$76,000.00	\$76,000.00
8	<b>Mobilization for Minor Streets (Bid Items 12, 16, and 81 thru 115), (P)</b>	1	LS	\$77,000.00	\$77,000.00
9	<b>Mobilization for Jurupa Avenue Storm Drain (Bid Items 13, 17, and 116 thru 118), (P)</b>	1	LS	\$7,430.50	\$7,430.50
10	<b>Mobilization for Exhibit H (Bid Items 14, 18, and 119 thru 127), (P)</b>	1	LS	\$7,000.00	\$7,000.00
11	<b>Water Pollution Control for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P)</b>	1	LS	\$2,900.00	\$2,900.00
12	<b>Water Pollution Control for Minor Streets (Bid Items 81 thru 115), (P)</b>	1	LS	\$2,000.00	\$2,000.00
13	<b>Water Pollution Control for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P)</b>	1	LS	\$2,000.00	\$2,000.00
14	<b>Water Pollution Control for Exhibit H (Bid Items 119 thru 127), (P)</b>	1	LS	\$2,000.00	\$2,000.00
15	<b>Traffic Control and Access for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$76,000.00	\$76,000.00
16	<b>Traffic Control and Access for Minor Streets (Bid Items 81 thru 115), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$77,000.00	\$77,000.00

17	<b>Traffic Control and Access for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$5,000.00	\$5,000.00
18	<b>Traffic Control and Access for Exhibit H (Bid Items 119 thru 127), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$5,000.00	\$5,000.00
<b>Sub-Total: Incidental Items</b>					\$339,330.50
<b>Arterial Street Maintenance (R-4336 and Exhibit G)</b>					
19	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,500	CY	\$50.00	\$125,000.00
20	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	1,300	CY	\$30.00	\$39,000.00
21	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,000	TON	\$77.00	\$154,000.00
22	<b>Unclassified Excavation for W. La Cadena Drive, (F).</b> (Includes approximately 100 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	120	CY	\$47.00	\$5,640.00
23	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b>	3,500	LF	\$2.00	\$7,000.00
24	<b>Cold Milling - Type CM2 (Depth Varies Per Plan).</b>	730,000	SF	\$0.17	\$124,100.00
25	<b>Cold Milling - Type CM3 (Full Depth).</b>	15,000	SF	\$1.49	\$22,350.00
26	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans. Includes median removals when required.)	7,200	TON	\$60.00	\$432,000.00
27	<b>Asphalt Rubber Hot Mix - Gap Graded (ARHM-GG) (0.12' min.) Overlay</b>	7,500	TON	\$74.00	\$555,000.00
28	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F).</b> (Applies to all surface treatment locations regardless if a median exists or not.)	14,000	LF	\$1.50	\$21,000.00
29	<b>Adjust Manhole Cover to Grade.</b> (Includes Electric, Telephone, Sewer, and Storm Drain manhole covers, and grate inlets.)	90	EA	\$700.00	\$63,000.00
30	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade.</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	100	EA	\$550.00	\$55,000.00
31	<b>Adjust Electric Manhole Vault Frame to Grade.</b> (Includes any adjustment/protection necessary for top to sit flush or 1/4" above finished grade. Includes proper electrical licensing.)	9	EA	\$3,250.00	\$29,250.00
32	<b>Concrete Curb and Gutter per City Std. 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on the plans.)	3,750	LF	\$40.00	\$150,000.00
33	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	210	LF	\$77.00	\$16,170.00
34	<b>Cobblestone Curb and Gutter per Part 10 of the Special Provisions</b>	500	LF	\$60.00	\$30,000.00
35	<b>Concrete Retaining Curb. (0"-18")</b>	550	LF	\$30.00	\$16,500.00
36	<b>Construct AC Berm per City Std. 250.</b> (Includes W. La Cadena Avenue and Central Avenue in locations as indicated on the plans or if necessary. Also includes hand forming where necessary.)	600	LF	\$15.00	\$9,000.00
37	<b>Concrete Cross Gutter per City Std. 220.</b> (Includes all modifications as indicated.)	5,000	SF	\$11.00	\$55,000.00
38	<b>Concrete Driveway per City Std. 302.</b> (Includes all modifications as indicated.)	10,000	SF	\$10.00	\$100,000.00

39	<b>PCC Pedestrian Ramp per City Std. 304 or Caltrans Standard Plan A88A.</b> (Type per plan, includes any modifications as necessary.)	65	EA	\$2,800.00	\$182,000.00
40	<b>PCC Sidewalk per City Std. 325.</b> (Includes parkway slope grading in conformance with City Std. 325.)	25,500	SF	\$6.25	\$159,375.00
41	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	550	SF	\$8.00	\$4,400.00
42	<b>R&amp;R Catch Basin Apron Only, per City Std. 405</b>	1	EA	\$10,000.00	\$10,000.00
43	<b>Parkway Drain per City Std. 410</b>	2	EA	\$3,000.00	\$6,000.00
44	<b>Concrete Pavement Section on Rivera Street</b>	1,150	SF	\$15.00	\$17,250.00
45	<b>Concrete Bus Pad per Detail in Special Provisions</b>	14	EA	\$14,000.00	\$196,000.00
46	<b>3.5" Thick Concrete Median</b>	25	SF	\$50.00	\$1,250.00
47	<b>Decorative White Rock for Tree Wells on Central Avenue.</b> (Includes clearing tree wells of dirt, debris, stumps, and tripping hazards.)	10	CY	\$500.00	\$5,000.00
48	<b>Crushed Rock Permeable Tree Well, (S).</b> (Includes training, all subsurface preparation, geogrids, aggregates, resins, and installation. Well sizes range from 16 SF to 54 SF. Total square footage for selected tree wells is 1600 SF. Product type must match Rockpave FlowStone "Desert Rose" from Exhibit C in Part 10 of the Special Provisions, or City approved equal.)	39	EA	\$1,000.00	\$39,000.00
49	<b>Exhibit G - Unclassified Excavation for Slope Restoration at Canyon Ridge Drive and Van Buren Blvd, (F).</b> (Includes approximately 50 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	800	CY	\$47.50	\$38,000.00
50	<b>Exhibit G - Import Fill, (F).</b> (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	375	CY	\$47.50	\$17,812.50
51	<b>Exhibit G - White Vinyl Fence.</b> (Type and color shall match existing. Includes all work to connect to existing fence as indicated on Exhibit G in Part 10 of the Special Provisions.)	25	LF	\$1.00	\$25.00
52	<b>Exhibit G - Hydroseed.</b> (Includes 365 days of hydroseed establishment.)	5,000	SF	\$7.00	\$35,000.00
<b>Sub-Total: Arterial Street Maintenance (R-4346 and Exhibit G)</b>					<b>\$2,720,122.50</b>
<b>Arterial Traffic Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					
53	<b>Install Sign (No Post), (S)</b>	3	EA	\$125.00	\$375.00
54	<b>Install Sign (One Post), (S)</b>	22	EA	\$190.00	\$4,180.00
55	<b>Install Street Name Sign, (S)</b>	21	EA	\$300.00	\$6,300.00
56	<b>Remove Sign, (S)</b>	29	EA	\$65.00	\$1,885.00
57	<b>4" Dashed White Stripe (Thermo) - Detail 9 w/ RPM(s), (S)</b>	21,020	LF	\$0.30	\$6,306.00
58	<b>Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)</b>	10,010	LF	\$0.70	\$7,007.00
59	<b>Detail 26 - (RPM's)</b>	400	LF	\$1.00	\$400.00
60	<b>4" Solid White Stripe (Thermo) - Detail 27B, (S)</b>	2,840	LF	\$0.40	\$1,136.00
61	<b>Double Yellow Median Island Stripe (Thermo) - Detail 29 w/ RPM(s), (S)</b>	1,210	LF	\$1.15	\$1,391.50
62	<b>Two Way Left Turn Stripe (Thermo) - Detail 32 w/ RPM(s), (S)</b>	2,765	LF	\$1.35	\$3,732.75
63	<b>Exit Ramp Neutral Area (Thermo) - Detail 36 w/ RPMs, (S)</b>	345	LF	\$1.20	\$414.00
64	<b>8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)</b>	1,925	LF	\$0.90	\$1,732.50
65	<b>8" Solid White Stripe (Thermo) - Detail 38A, (S)</b>	200	LF	\$0.90	\$180.00
66	<b>8" Solid White Stripe (Thermo) - Detail 39, (S)</b>	16,435	LF	\$0.40	\$6,574.00
67	<b>8" Solid White Stripe (Thermo) - Detail 39A, (S)</b>	2,620	LF	\$0.40	\$1,048.00
68	<b>4" Dashed White Stripe (Thermo) - Detail 40, (S)</b>	665	LF	\$0.35	\$232.75
69	<b>4" Solid Stripe (Thermo), (S)</b>	3,110	LF	\$0.40	\$1,244.00
70	<b>6" Solid Stripe (Thermo), (S)</b>	755	LF	\$0.65	\$490.75

71	<b>12" Solid Stripe (Thermo), (S)</b>	5,240	SF	\$1.25	\$6,550.00
72	<b>Pavement Markings (Thermo), (S)</b>	3,090	SF	\$2.45	\$7,570.50
73	<b>Paint Median Nose w/ RPM(s), (S)</b>	3	EA	\$133.00	\$399.00
74	<b>Paint Curb (Red, White, or Yellow), (S)</b>	285	LF	\$1.05	\$299.25
75	<b>Type "C" Detector Loop, (S)</b>	6	EA	\$750.00	\$4,500.00
76	<b>Type "D" Detector Loop, (S)</b>	51	EA	\$235.00	\$11,985.00
77	<b>Type "E" Detector Loop, (S)</b>	117	EA	\$210.00	\$24,570.00
78	<b>SC - Splice new to existing conductors, (S)</b>	33	EA	\$20.00	\$660.00
79	<b>DLC - Detector Loop Cable, (S)</b>	2,895	LF	\$2.10	\$6,079.50
80	<b>2-Channel Detector Card, (S)</b>	13	EA	\$280.00	\$3,640.00
<b>Sub-Total: Arterial Street Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					<b>\$110,882.50</b>
<b>Minor Street Maintenance And Traffic Improvements (R-4346 and R-4351)</b>					
81	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b> (Includes variable grind when indicated)	510	LF	\$2.00	\$1,020.00
82	<b>Cold Milling, Type CM2 (Depth Varies Per Plan)</b> (Includes variable grind when indicated)	290,000	SF	\$0.24	\$69,600.00
83	<b>Cold Milling, Type CM3 (Full Depth)</b>	52,000	SF	\$1.49	\$77,480.00
84	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F)</b> (Includes all areas to receive Slurry Seal, ARAM treatment, and Cold Milling Type CM1/CM2.)	101,000	LF	\$0.77	\$77,770.00
85	<b>Crushed Aggregate Base, (F)</b>	1,070	CY	\$66.00	\$70,620.00
86	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans and slot patches.)	4,010	TONS	\$69.00	\$276,690.00
87	<b>Construct Asphalt Rubber Aggregate Membrane (ARAM) (S)</b>	2,980,000	SF	\$0.45	\$1,341,000.00
88	<b>Construct Slurry Seal, Type II</b>	2,980,000	SF	\$0.15	\$447,000.00
89	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	1,500	CY	\$50.00	\$75,000.00
90	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	500	CY	\$30.00	\$15,000.00
91	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	250	TN	\$150.00	\$37,500.00
92	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	300	EA	\$275.00	\$82,500.00
93	<b>Adjust Manhole to Grade</b> (Includes Electric, Water, Sewer, and Storm Drain manhole covers)	385	EA	\$525.00	\$202,125.00
94	<b>Concrete Curb and Gutter per City Std 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on plans.)	2,600	LF	\$40.00	\$104,000.00
95	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	1,400	LF	\$77.00	\$107,800.00
96	<b>Concrete Cross Gutter per Std 220</b> (Includes ribbon gutters and all modifications as indicated.)	4,000	SF	\$11.00	\$44,000.00
97	<b>Concrete Driveway per City Std 302.</b> (Includes all modifications as indicated.)	1,200	SF	\$10.00	\$12,000.00
98	<b>PCC Pedstrian Ramp per City Std 304.</b> (Type per plan, includes any modifications as necessary.)	275	EA	\$2,800.00	\$770,000.00
99	<b>PCC Pedstrian Ramp per City Std 304, Type VII</b>	1,450	SF	\$10.00	\$14,500.00
100	<b>PCC Sidewalk per City Std 325</b> (Includes parkway slope grading in conformance with the plans and the Standard 325. Also includes sidewalk of 6" thickness where indicated or required for the driveway approach. Includes furnishing and installing traffic rated boxes and lids when indicated)	35,000	SF	\$6.25	\$218,750.00
101	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	1,200	SF	\$8.00	\$9,600.00

102	Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)	8,835	LF	\$0.70	\$6,184.50
103	4" Solid White Stripe (Thermo) - Detail 27B, (S)	595	LF	\$0.40	\$238.00
104	8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)	65	LF	\$0.90	\$58.50
105	12" Solid Stripe White or Yellow (Thermo), (S)	6,150	SF	\$1.25	\$7,687.50
106	Pavement Legends / Markings (Thermo), (S)	4,475	SF	\$2.45	\$10,963.75
107	Type "G" Markers, (S)	17	EA	\$4.75	\$80.75
108	Type "D" Detector Loop, (S)	9	EA	\$235.00	\$2,115.00
109	Remove Sign (No Post), (S)	31	EA	\$40.00	\$1,240.00
110	Remove Sign (One Post), (S)	193	EA	\$65.00	\$12,545.00
111	Install Sign (No Post), (S)	37	EA	\$120.00	\$4,440.00
112	Install Sign (One Post), (S)	126	EA	\$190.00	\$23,940.00
113	Install Street Name Sign, (S)	123	EA	\$300.00	\$36,900.00
114	Relocate Sign (No Post), (S)	22	EA	\$50.00	\$1,100.00
115	Relocate Sign (One Post), (S)	2	EA	\$125.00	\$250.00
<b>Sub-Total: Minor Street Maintenance and Traffic Improvements (R-4346 and R-4351)</b>					<b>\$4,161,698.00</b>
<b>Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					
116	Furnish and Install 18" RCP Pipe. (Includes pre and post inspection video requirements, PWS connection at the existing RCB, and all requirements as described in the Special Provisions.)	66	LF	\$700.00	\$46,200.00
117	Construct Catch Basin per City Std 405, W=8'	1	EA	\$7,000.00	\$7,000.00
118	Construct Concrete Sidewalk per City Std 325	325	SF	\$6.00	\$1,950.00
<b>Sub-Total: Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					<b>\$55,150.00</b>
<b>Fountain Demolition and Landscape Improvements (Exhibit H)</b>					
119	Concrete / Cobble Fountain Structure Demolition (Includes all labor and equipment for demolition and proper disposal)	1	LS	\$24,000.00	\$24,000.00
120	Soil Preparation/Fine Grading	2,200	SF	\$3.00	\$6,600.00
121	Import Fill, (F). (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	175	CY	\$47.50	\$8,312.50
122	Top Soil, (F)	20	CY	\$77.00	\$1,540.00
123	Wood Mulch (2" Layer)	2,200	SF	\$0.77	\$1,694.00
124	Sod	120	SF	\$2.00	\$240.00
125	1 Gallon Drought Tolerant Plantings	130	EA	\$11.00	\$1,430.00
126	Design, Furnish & Install/Modify Irrigation System	1	LS	\$11,000.00	\$11,000.00
127	NDS atrium grate and cleanout box, 3" pvc pipes, Curb outlet, and coring.	1	LS	\$5,000.00	\$5,000.00
<b>Sub-Total: Fountain Demolition and Landscape Improvements (Exhibit H)</b>					<b>\$59,816.50</b>
					<b>Bid Total</b>
					<b>\$7,447,000.00</b>

<b>Subcontractor Information</b>			
<b>Subcontractor Name</b>	<b>Location</b>	<b>Portion</b>	<b>Amount</b>
EBS Utilities	Corona, CA	Manhole	\$367,775.00
Covarrubia's Bro's Construction	Murrieta, CA	Catch Basin	\$52,514.00
Manhole Advertising Inc.	Pico Rivera, CA	ARAM	\$1,442,660.00
Phoenix Landscape	Fullerton, CA	Landscape	\$53,363.20

Cal Stripe	Colton, CA	Striping	\$165,076.00
All American Asphalt	Corona, CA	Slurry Seal	\$447,000.00
California Professional Engineering	La Puente, CA	Detector Loops	\$53,549.50

# BID RESULTS

City of Riverside  
Finance Dept./Purchasing

Due Date	1/13/2016	Bid No.	7354
Before	2:00pm	Estimate	\$7,698,994.25

## Bid Description

2015/2016 Arterial and Minor Streets Maintenance

### Bidder

Griffith Company

Item No.	Item Description	Qty	Unit	Unit Price	Ext. Price
<b>Incidental Items</b>					
1	<b>Note:</b> All items subject to any special notes or footnotes appearing on this Engineer's estimate included with the bid documents.	...	...	...	...
2	<b>Note:</b> The Contract lump sum or unit price for each Contract Bid Item shall include full compensation for all labor, materials, tools, taxes, profit, overhead, incidentals and appurtenant work necessary for performing and completing the work of the Contract Bid Item as required by the Project Plans, Specifications, Special Provisions and other Contract Documents. Such compensation shall also include or take into consideration any additional provisions or conditions specifically stated immediately following the Contract Bid Item.	...	...	...	...
3	<b>Note:</b> In the absence of a specific bid item or specific payment provisions for any portion of the work required by the Contract Documents, the bidder shall include the bidder's compensation for that portion of the Contract work in the Contract unit price(s) and/or lump sum price(s) of the bid item(s) that require such work, or are closely related to such work. Therefore, no separate or additional payment will be made to the Contractor for any such work on the premise that such work lacks specific bid item(s) or specific payment provisions.	...	...	...	...
4	<b>Note:</b> "(P)" adjacent to a Contract bid item designates a "Partial Pay Item" per Section 9-3.2 of the Special Provisions.	...	...	...	...
5	<b>Note:</b> "(F)" adjacent to a Contract bid item designates a Final Pay Quantity per Section 9-3.2.1 of the Special Provisions.	...	...	...	...
6	<b>Note:</b> "(S)" adjacent to a Contract bid item designates a "Specialty Item" per Section 2-3.2 of the Special Provisions.	...	...	...	...
7	<b>Mobilization for Arterial Streets &amp; Exhibit G (Bid Items 11, 15, and 19 thru 80), (P)</b>	1	LS	\$19,000.00	\$19,000.00
8	<b>Mobilization for Minor Streets (Bid Items 12, 16, and 81 thru 115), (P)</b>	1	LS	\$47,000.00	\$47,000.00
9	<b>Mobilization for Jurupa Avenue Storm Drain (Bid Items 13, 17, and 116 thru 118), (P)</b>	1	LS	\$29,000.00	\$29,000.00
10	<b>Mobilization for Exhibit H (Bid Items 14, 18, and 119 thru 127), (P)</b>	1	LS	\$20,000.00	\$20,000.00
11	<b>Water Pollution Control for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P)</b>	1	LS	\$6,000.00	\$6,000.00
12	<b>Water Pollution Control for Minor Streets (Bid Items 81 thru 115), (P)</b>	1	LS	\$12,000.00	\$12,000.00
13	<b>Water Pollution Control for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P)</b>	1	LS	\$3,500.00	\$3,500.00
14	<b>Water Pollution Control for Exhibit H (Bid Items 119 thru 127), (P)</b>	1	LS	\$3,500.00	\$3,500.00
15	<b>Traffic Control and Access for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$40,000.00	\$40,000.00
16	<b>Traffic Control and Access for Minor Streets (Bid Items 81 thru 115), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$52,300.00	\$52,300.00

17	<b>Traffic Control and Access for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$3,500.00	\$3,500.00
18	<b>Traffic Control and Access for Exhibit H (Bid Items 119 thru 127), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$3,500.00	\$3,500.00
<b>Sub-Total: Incidental Items</b>					\$239,300.00
<b>Arterial Street Maintenance (R-4336 and Exhibit G)</b>					
19	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,500	CY	\$39.00	\$97,500.00
20	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	1,300	CY	\$44.00	\$57,200.00
21	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,000	TON	\$170.00	\$340,000.00
22	<b>Unclassified Excavation for W. La Cadena Drive, (F).</b> (Includes approximately 100 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	120	CY	\$100.00	\$12,000.00
23	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b>	3,500	LF	\$1.70	\$5,950.00
24	<b>Cold Milling - Type CM2 (Depth Varies Per Plan).</b>	730,000	SF	\$0.27	\$197,100.00
25	<b>Cold Milling - Type CM3 (Full Depth).</b>	15,000	SF	\$0.36	\$5,400.00
26	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans. Includes median removals when required.)	7,200	TON	\$65.50	\$471,600.00
27	<b>Asphalt Rubber Hot Mix - Gap Graded (ARHM-GG) (0.12' min.) Overlay</b>	7,500	TON	\$81.00	\$607,500.00
28	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F).</b> (Applies to all surface treatment locations regardless if a median exists or not.)	14,000	LF	\$3.50	\$49,000.00
29	<b>Adjust Manhole Cover to Grade.</b> (Includes Electric, Telephone, Sewer, and Storm Drain manhole covers, and grate inlets.)	90	EA	\$745.00	\$67,050.00
30	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade.</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	100	EA	\$580.00	\$58,000.00
31	<b>Adjust Electric Manhole Vault Frame to Grade.</b> (Includes any adjustment/protection necessary for top to sit flush or 1/4" above finished grade. Includes proper electrical licensing.)	9	EA	\$3,500.00	\$31,500.00
32	<b>Concrete Curb and Gutter per City Std. 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on the plans.)	3,750	LF	\$45.00	\$168,750.00
33	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	210	LF	\$95.00	\$19,950.00
34	<b>Cobblestone Curb and Gutter per Part 10 of the Special Provisions</b>	500	LF	\$87.00	\$43,500.00
35	<b>Concrete Retaining Curb. (0"-18")</b>	550	LF	\$23.00	\$12,650.00
36	<b>Construct AC Berm per City Std. 250.</b> (Includes W. La Cadena Avenue and Central Avenue in locations as indicated on the plans or if necessary. Also includes hand forming where necessary.)	600	LF	\$9.00	\$5,400.00
37	<b>Concrete Cross Gutter per City Std. 220.</b> (Includes all modifications as indicated.)	5,000	SF	\$11.00	\$55,000.00
38	<b>Concrete Driveway per City Std. 302.</b> (Includes all modifications as indicated.)	10,000	SF	\$10.00	\$100,000.00

39	<b>PCC Pedestrian Ramp per City Std. 304 or Caltrans Standard Plan A88A.</b> (Type per plan, includes any modifications as necessary.)	65	EA	\$2,400.00	\$156,000.00
40	<b>PCC Sidewalk per City Std. 325.</b> (Includes parkway slope grading in conformance with City Std. 325.)	25,500	SF	\$6.50	\$165,750.00
41	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	550	SF	\$9.00	\$4,950.00
42	<b>R&amp;R Catch Basin Apron Only, per City Std. 405</b>	1	EA	\$4,600.00	\$4,600.00
43	<b>Parkway Drain per City Std. 410</b>	2	EA	\$5,200.00	\$10,400.00
44	<b>Concrete Pavement Section on Rivera Street</b>	1,150	SF	\$10.00	\$11,500.00
45	<b>Concrete Bus Pad per Detail in Special Provisions</b>	14	EA	\$12,000.00	\$168,000.00
46	<b>3.5" Thick Concrete Median</b>	25	SF	\$43.00	\$1,075.00
47	<b>Decorative White Rock for Tree Wells on Central Avenue.</b> (Includes clearing tree wells of dirt, debris, stumps, and tripping hazards.)	10	CY	\$820.00	\$8,200.00
48	<b>Crushed Rock Permeable Tree Well, (S).</b> (Includes training, all subsurface preparation, geogrids, aggregates, resins, and installation. Well sizes range from 16 SF to 54 SF. Total square footage for selected tree wells is 1600 SF. Product type must match Rockpave FlowStone "Desert Rose" from Exhibit C in Part 10 of the Special Provisions, or City approved equal.)	39	EA	\$1,200.00	\$46,800.00
49	<b>Exhibit G - Unclassified Excavation for Slope Restoration at Canyon Ridge Drive and Van Buren Blvd, (F).</b> (Includes approximately 50 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	800	CY	\$75.00	\$60,000.00
50	<b>Exhibit G - Import Fill, (F).</b> (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	375	CY	\$100.00	\$37,500.00
51	<b>Exhibit G - White Vinyl Fence.</b> (Type and color shall match existing. Includes all work to connect to existing fence as indicated on Exhibit G in Part 10 of the Special Provisions.)	25	LF	\$100.00	\$2,500.00
52	<b>Exhibit G - Hydroseed.</b> (Includes 365 days of hydroseed establishment.)	5,000	SF	\$1.75	\$8,750.00
<b>Sub-Total: Arterial Street Maintenance (R-4346 and Exhibit G)</b>					<b>\$3,091,075.00</b>
<b>Arterial Traffic Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					
53	<b>Install Sign (No Post), (S)</b>	3	EA	\$127.00	\$381.00
54	<b>Install Sign (One Post), (S)</b>	22	EA	\$263.00	\$5,786.00
55	<b>Install Street Name Sign, (S)</b>	21	EA	\$350.00	\$7,350.00
56	<b>Remove Sign, (S)</b>	29	EA	\$48.00	\$1,392.00
57	<b>4" Dashed White Stripe (Thermo) - Detail 9 w/ RPM(s), (S)</b>	21,020	LF	\$0.45	\$9,459.00
58	<b>Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)</b>	10,010	LF	\$1.30	\$13,013.00
59	<b>Detail 26 - (RPM's)</b>	400	LF	\$0.53	\$212.00
60	<b>4" Solid White Stripe (Thermo) - Detail 27B, (S)</b>	2,840	LF	\$0.45	\$1,278.00
61	<b>Double Yellow Median Island Stripe (Thermo) - Detail 29 w/ RPM(s), (S)</b>	1,210	LF	\$2.40	\$2,904.00
62	<b>Two Way Left Trun Stripe (Thermo) - Detail 32 w/ RPM(s), (S)</b>	2,765	LF	\$2.40	\$6,636.00
63	<b>Exit Ramp Neutral Area (Thermo) - Detail 36 w/ RPMs, (S)</b>	345	LF	\$1.10	\$379.50
64	<b>8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)</b>	1,925	LF	\$1.10	\$2,117.50
65	<b>8" Solid White Stripe (Thermo) - Detail 38A, (S)</b>	200	LF	\$1.00	\$200.00
66	<b>8" Solid White Stripe (Thermo) - Detail 39, (S)</b>	16,435	LF	\$0.85	\$13,969.75
67	<b>8" Solid White Stripe (Thermo) - Detail 39A, (S)</b>	2,620	LF	\$0.85	\$2,227.00
68	<b>4" Dashed White Stripe (Thermo) - Detail 40, (S)</b>	665	LF	\$2.10	\$1,396.50
69	<b>4" Solid Stripe (Thermo), (S)</b>	3,110	LF	\$1.60	\$4,976.00
70	<b>6" Solid Stripe (Thermo), (S)</b>	755	LF	\$2.10	\$1,585.50

71	<b>12" Solid Stripe (Thermo), (S)</b>	5,240	SF	\$3.00	\$15,720.00
72	<b>Pavement Markings (Thermo), (S)</b>	3,090	SF	\$3.40	\$10,506.00
73	<b>Paint Median Nose w/ RPM(s), (S)</b>	3	EA	\$106.00	\$318.00
74	<b>Paint Curb (Red, White, or Yellow), (S)</b>	285	LF	\$1.60	\$456.00
75	<b>Type "C" Detector Loop, (S)</b>	6	EA	\$800.00	\$4,800.00
76	<b>Type "D" Detector Loop, (S)</b>	51	EA	\$250.00	\$12,750.00
77	<b>Type "E" Detector Loop, (S)</b>	117	EA	\$225.00	\$26,325.00
78	<b>SC - Splice new to existing conductors, (S)</b>	33	EA	\$21.00	\$693.00
79	<b>DLC - Detector Loop Cable, (S)</b>	2,895	LF	\$2.30	\$6,658.50
80	<b>2-Channel Detector Card, (S)</b>	13	EA	\$300.00	\$3,900.00
<b>Sub-Total: Arterial Street Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					<b>\$157,389.25</b>
<b>Minor Street Maintenance And Traffic Improvements (R-4346 and R-4351)</b>					
81	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b> (Includes variable grind when indicated)	510	LF	\$1.70	\$867.00
82	<b>Cold Milling, Type CM2 (Depth Varies Per Plan)</b> (Includes variable grind when indicated)	290,000	SF	\$0.27	\$78,300.00
83	<b>Cold Milling, Type CM3 (Full Depth)</b>	52,000	SF	\$0.36	\$18,720.00
84	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F)</b> (Includes all areas to receive Slurry Seal, ARAM treatment, and Cold Milling Type CM1/CM2.)	101,000	LF	\$2.20	\$222,200.00
85	<b>Crushed Aggregate Base, (F)</b>	1,070	CY	\$25.00	\$26,750.00
86	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans and slot patches.)	4,010	TONS	\$65.50	\$262,655.00
87	<b>Construct Asphalt Rubber Aggregate Membrane (ARAM) (S)</b>	2,980,000	SF	\$0.42	\$1,251,600.00
88	<b>Construct Slurry Seal, Type II</b>	2,980,000	SF	\$0.19	\$566,200.00
89	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	1,500	CY	\$39.00	\$58,500.00
90	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	500	CY	\$44.00	\$22,000.00
91	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	250	TN	\$91.00	\$22,750.00
92	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	300	EA	\$313.00	\$93,900.00
93	<b>Adjust Manhole to Grade</b> (Includes Electric, Water, Sewer, and Storm Drain manhole covers)	385	EA	\$365.00	\$140,525.00
94	<b>Concrete Curb and Gutter per City Std 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on plans.)	2,600	LF	\$45.00	\$117,000.00
95	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	1,400	LF	\$95.00	\$133,000.00
96	<b>Concrete Cross Gutter per Std 220</b> (Includes ribbon gutters and all modifications as indicated.)	4,000	SF	\$11.00	\$44,000.00
97	<b>Concrete Driveway per City Std 302.</b> (Includes all modifications as indicated.)	1,200	SF	\$9.00	\$10,800.00
98	<b>PCC Pedstrian Ramp per City Std 304.</b> (Type per plan, includes any modifications as necessary.)	275	EA	\$2,100.00	\$577,500.00
99	<b>PCC Pedstrian Ramp per City Std 304, Type VII</b>	1,450	SF	\$10.00	\$14,500.00
100	<b>PCC Sidewalk per City Std 325</b> (Includes parkway slope grading in conformance with the plans and the Standard 325. Also includes sidewalk of 6" thickness where indicated or required for the driveway approach. Includes furnishing and installing traffic rated boxes and lids when indicated)	35,000	SF	\$6.80	\$238,000.00
101	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	1,200	SF	\$9.00	\$10,800.00

102	Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)	8,835	LF	\$1.25	\$11,043.75
103	4" Solid White Stripe (Thermo) - Detail 27B, (S)	595	LF	\$0.55	\$327.25
104	8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)	65	LF	\$2.10	\$136.50
105	12" Solid Stripe White or Yellow (Thermo), (S)	6,150	SF	\$3.00	\$18,450.00
106	Pavement Legends / Markings (Thermo), (S)	4,475	SF	\$3.40	\$15,215.00
107	Type "G" Markers, (S)	17	EA	\$3.00	\$51.00
108	Type "D" Detector Loop, (S)	9	EA	\$250.00	\$2,250.00
109	Remove Sign (No Post), (S)	31	EA	\$48.00	\$1,488.00
110	Remove Sign (One Post), (S)	193	EA	\$64.00	\$12,352.00
111	Install Sign (No Post), (S)	37	EA	\$125.00	\$4,625.00
112	Install Sign (One Post), (S)	126	EA	\$260.00	\$32,760.00
113	Install Street Name Sign, (S)	123	EA	\$350.00	\$43,050.00
114	Relocate Sign (No Post), (S)	22	EA	\$125.00	\$2,750.00
115	Relocate Sign (One Post), (S)	2	EA	\$190.00	\$380.00
<b>Sub-Total: Minor Street Maintenance and Traffic Improvements (R-4346 and R-4351)</b>					<b>\$4,055,445.50</b>
<b>Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					
116	Furnish and Install 18" RCP Pipe. (Includes pre and post inspection video requirements, PWS connection at the existing RCB, and all requirements as described in the Special Provisions.)	66	LF	\$460.00	\$30,360.00
117	Construct Catch Basin per City Std 405, W=8'	1	EA	\$7,400.00	\$7,400.00
118	Construct Concrete Sidewalk per City Std 325	325	SF	\$9.51	\$3,090.75
<b>Sub-Total: Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					<b>\$40,850.75</b>
<b>Fountain Demolition and Landscape Improvements (Exhibit H)</b>					
119	Concrete / Cobble Fountain Structure Demolition (Includes all labor and equipment for demolition and proper disposal)	1	LS	\$13,000.00	\$13,000.00
120	Soil Preparation/Fine Grading	2,200	SF	\$5.00	\$11,000.00
121	Import Fill, (F). (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	175	CY	\$200.00	\$35,000.00
122	Top Soil, (F)	20	CY	\$250.00	\$5,000.00
123	Wood Mulch (2" Layer)	2,200	SF	\$1.00	\$2,200.00
124	Sod	120	SF	\$5.00	\$600.00
125	1 Gallon Drought Tolerant Plantings	130	EA	\$20.00	\$2,600.00
126	Design, Furnish & Install/Modify Irrigation System	1	LS	\$15,000.00	\$15,000.00
127	NDS atrium grate and cleanout box, 3" pvc pipes, Curb outlet, and coring.	1	LS	\$10,000.00	\$10,000.00
<b>Sub-Total: Fountain Demolition and Landscape Improvements (Exhibit H)</b>					<b>\$94,400.00</b>
<b>Bid Total</b>					<b>\$7,678,460.50</b>

<b>Subcontractor Information</b>			
<b>Subcontractor Name</b>	<b>Location</b>	<b>Portion</b>	<b>Amount</b>
American Pavement Systems	Modesto, CA	Asphalt	\$1,311,880.00
EBS General Engineering, Inc.	Corona, CA	Adjust Utilities	\$367,775.00
Cal-Stripe	Colton, CA	Sign & Stripe	\$165,076.00
All American Asphalt	Corona, CA	Coldmill & Slurry	\$640,000.00

CL Concrete	Azusa, CA	Concrete	\$1,330,000.00
Global Road Sealing	Garden Grove, CA	Loops and Crackseal	\$292,000.00
SRD	Anaheim, CA	Storm Drain	\$44,180.00

# BID RESULTS

City of Riverside  
Finance Dept./Purchasing

Due Date	1/13/2016	Bid No.	7354
Before	2:00pm	Estimate	\$7,698,994.25

## Bid Description

2015/2016 Arterial and Minor Streets Maintenance

### Bidder

R.J. Noble Company

Item No.	Item Description	Qty	Unit	Unit Price	Ext. Price
<b>Incidental Items</b>					
1	<b>Note:</b> All items subject to any special notes or footnotes appearing on this Engineer's estimate included with the bid documents.	...	...	...	...
2	<b>Note:</b> The Contract lump sum or unit price for each Contract Bid Item shall include full compensation for all labor, materials, tools, taxes, profit, overhead, incidentals and appurtenant work necessary for performing and completing the work of the Contract Bid Item as required by the Project Plans, Specifications, Special Provisions and other Contract Documents. Such compensation shall also include or take into consideration any additional provisions or conditions specifically stated immediately following the Contract Bid Item.	...	...	...	...
3	<b>Note:</b> In the absence of a specific bid item or specific payment provisions for any portion of the work required by the Contract Documents, the bidder shall include the bidder's compensation for that portion of the Contract work in the Contract unit price(s) and/or lump sum price(s) of the bid item(s) that require such work, or are closely related to such work. Therefore, no separate or additional payment will be made to the Contractor for any such work on the premise that such work lacks specific bid item(s) or specific payment provisions.	...	...	...	...
4	<b>Note: "(P)"</b> adjacent to a Contract bid item designates a "Partial Pay Item" per Section 9-3.2 of the Special Provisions.	...	...	...	...
5	<b>Note: "(F)"</b> adjacent to a Contract bid item designates a Final Pay Quantity per Section 9-3.2.1 of the Special Provisions.	...	...	...	...
6	<b>Note: "(S)"</b> adjacent to a Contract bid item designates a "Specialty Item" per Section 2-3.2 of the Special Provisions.	...	...	...	...
7	<b>Mobilization for Arterial Streets &amp; Exhibit G (Bid Items 11, 15, and 19 thru 80), (P)</b>	1	LS	\$95,000.00	\$95,000.00
8	<b>Mobilization for Minor Streets (Bid Items 12, 16, and 81 thru 115), (P)</b>	1	LS	\$95,000.00	\$95,000.00
9	<b>Mobilization for Jurupa Avenue Storm Drain (Bid Items 13, 17, and 116 thru 118), (P)</b>	1	LS	\$15,000.00	\$15,000.00
10	<b>Mobilization for Exhibit H (Bid Items 14, 18, and 119 thru 127), (P)</b>	1	LS	\$5,500.00	\$5,500.00
11	<b>Water Pollution Control for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P)</b>	1	LS	\$17,000.00	\$17,000.00
12	<b>Water Pollution Control for Minor Streets (Bid Items 81 thru 115), (P)</b>	1	LS	\$17,000.00	\$17,000.00
13	<b>Water Pollution Control for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P)</b>	1	LS	\$7,400.00	\$7,400.00
14	<b>Water Pollution Control for Exhibit H (Bid Items 119 thru 127), (P)</b>	1	LS	\$4,400.00	\$4,400.00
15	<b>Traffic Control and Access for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$45,000.00	\$45,000.00
16	<b>Traffic Control and Access for Minor Streets (Bid Items 81 thru 115), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$105,000.00	\$105,000.00

17	<b>Traffic Control and Access for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$8,800.00	\$8,800.00
18	<b>Traffic Control and Access for Exhibit H (Bid Items 119 thru 127), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$7,300.00	\$7,300.00
<b>Sub-Total: Incidental Items</b>					\$422,400.00
<b>Arterial Street Maintenance (R-4336 and Exhibit G)</b>					
19	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,500	CY	\$36.00	\$90,000.00
20	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	1,300	CY	\$31.00	\$40,300.00
21	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,000	TON	\$65.00	\$130,000.00
22	<b>Unclassified Excavation for W. La Cadena Drive, (F).</b> (Includes approximately 100 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	120	CY	\$86.00	\$10,320.00
23	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b>	3,500	LF	\$4.30	\$15,050.00
24	<b>Cold Milling - Type CM2 (Depth Varies Per Plan).</b>	730,000	SF	\$0.20	\$146,000.00
25	<b>Cold Milling - Type CM3 (Full Depth).</b>	15,000	SF	\$0.39	\$5,850.00
26	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans. Includes median removals when required.)	7,200	TON	\$63.00	\$453,600.00
27	<b>Asphalt Rubber Hot Mix - Gap Graded (ARHM-GG) (0.12' min.) Overlay</b>	7,500	TON	\$72.00	\$540,000.00
28	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F).</b> (Applies to all surface treatment locations regardless if a median exists or not.)	14,000	LF	\$2.30	\$32,200.00
29	<b>Adjust Manhole Cover to Grade.</b> (Includes Electric, Telephone, Sewer, and Storm Drain manhole covers, and grate inlets.)	90	EA	\$340.00	\$30,600.00
30	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade.</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	100	EA	\$290.00	\$29,000.00
31	<b>Adjust Electric Manhole Vault Frame to Grade.</b> (Includes any adjustment/protection necessary for top to sit flush or 1/4" above finished grade. Includes proper electrical licensing.)	9	EA	\$2,100.00	\$18,900.00
32	<b>Concrete Curb and Gutter per City Std. 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on the plans.)	3,750	LF	\$51.00	\$191,250.00
33	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	210	LF	\$82.00	\$17,220.00
34	<b>Cobblestone Curb and Gutter per Part 10 of the Special Provisions</b>	500	LF	\$84.00	\$42,000.00
35	<b>Concrete Retaining Curb. (0"-18")</b>	550	LF	\$17.00	\$9,350.00
36	<b>Construct AC Berm per City Std. 250.</b> (Includes W. La Cadena Avenue and Central Avenue in locations as indicated on the plans or if necessary. Also includes hand forming where necessary.)	600	LF	\$9.25	\$5,550.00
37	<b>Concrete Cross Gutter per City Std. 220.</b> (Includes all modifications as indicated.)	5,000	SF	\$13.40	\$67,000.00
38	<b>Concrete Driveway per City Std. 302.</b> (Includes all modifications as indicated.)	10,000	SF	\$10.80	\$108,000.00

39	<b>PCC Pedestrian Ramp per City Std. 304 or Caltrans Standard Plan A88A.</b> (Type per plan, includes any modifications as necessary.)	65	EA	\$3,700.00	\$240,500.00
40	<b>PCC Sidewalk per City Std. 325.</b> (Includes parkway slope grading in conformance with City Std. 325.)	25,500	SF	\$7.50	\$191,250.00
41	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	550	SF	\$12.00	\$6,600.00
42	<b>R&amp;R Catch Basin Apron Only, per City Std. 405</b>	1	EA	\$4,100.00	\$4,100.00
43	<b>Parkway Drain per City Std. 410</b>	2	EA	\$4,100.00	\$8,200.00
44	<b>Concrete Pavement Section on Rivera Street</b>	1,150	SF	\$6.20	\$7,130.00
45	<b>Concrete Bus Pad per Detail in Special Provisions</b>	14	EA	\$13,600.00	\$190,400.00
46	<b>3.5" Thick Concrete Median</b>	25	SF	\$51.45	\$1,286.25
47	<b>Decorative White Rock for Tree Wells on Central Avenue.</b> (Includes clearing tree wells of dirt, debris, stumps, and tripping hazards.)	10	CY	\$130.00	\$1,300.00
48	<b>Crushed Rock Permeable Tree Well, (S).</b> (Includes training, all subsurface preparation, geogrids, aggregates, resins, and installation. Well sizes range from 16 SF to 54 SF. Total square footage for selected tree wells is 1600 SF. Product type must match Rockpave FlowStone "Desert Rose" from Exhibit C in Part 10 of the Special Provisions, or City approved equal.)	39	EA	\$1,100.00	\$42,900.00
49	<b>Exhibit G - Unclassified Excavation for Slope Restoration at Canyon Ridge Drive and Van Buren Blvd, (F).</b> (Includes approximately 50 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	800	CY	\$50.00	\$40,000.00
50	<b>Exhibit G - Import Fill, (F).</b> (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	375	CY	\$38.50	\$14,437.50
51	<b>Exhibit G - White Vinyl Fence.</b> (Type and color shall match existing. Includes all work to connect to existing fence as indicated on Exhibit G in Part 10 of the Special Provisions.)	25	LF	\$43.00	\$1,075.00
52	<b>Exhibit G - Hydroseed.</b> (Includes 365 days of hydroseed establishment.)	5,000	SF	\$7.20	\$36,000.00
<b>Sub-Total: Arterial Street Maintenance (R-4346 and Exhibit G)</b>					<b>\$2,767,368.75</b>
<b>Arterial Traffic Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					
53	<b>Install Sign (No Post), (S)</b>	3	EA	\$123.00	\$369.00
54	<b>Install Sign (One Post), (S)</b>	22	EA	\$255.00	\$5,610.00
55	<b>Install Street Name Sign, (S)</b>	21	EA	\$340.00	\$7,140.00
56	<b>Remove Sign, (S)</b>	29	EA	\$46.00	\$1,334.00
57	<b>4" Dashed White Stripe (Thermo) - Detail 9 w/ RPM(s), (S)</b>	21,020	LF	\$0.41	\$8,618.20
58	<b>Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)</b>	10,010	LF	\$0.98	\$9,809.80
59	<b>Detail 26 - (RPM's)</b>	400	LF	\$0.51	\$204.00
60	<b>4" Solid White Stripe (Thermo) - Detail 27B, (S)</b>	2,840	LF	\$0.41	\$1,164.40
61	<b>Double Yellow Median Island Stripe (Thermo) - Detail 29 w/ RPM(s), (S)</b>	1,210	LF	\$2.40	\$2,904.00
62	<b>Two Way Left Trun Stripe (Thermo) - Detail 32 w/ RPM(s), (S)</b>	2,765	LF	\$2.40	\$6,636.00
63	<b>Exit Ramp Neutral Area (Thermo) - Detail 36 w/ RPMs, (S)</b>	345	LF	\$1.05	\$362.25
64	<b>8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)</b>	1,925	LF	\$1.05	\$2,021.25
65	<b>8" Solid White Stripe (Thermo) - Detail 38A, (S)</b>	200	LF	\$0.95	\$190.00
66	<b>8" Solid White Stripe (Thermo) - Detail 39, (S)</b>	16,435	LF	\$0.76	\$12,490.60
67	<b>8" Solid White Stripe (Thermo) - Detail 39A, (S)</b>	2,620	LF	\$0.82	\$2,148.40
68	<b>4" Dashed White Stripe (Thermo) - Detail 40, (S)</b>	665	LF	\$2.05	\$1,363.25
69	<b>4" Solid Stripe (Thermo), (S)</b>	3,110	LF	\$1.55	\$4,820.50
70	<b>6" Solid Stripe (Thermo), (S)</b>	755	LF	\$2.10	\$1,585.50

71	<b>12" Solid Stripe (Thermo), (S)</b>	5,240	SF	\$1.50	\$7,860.00
72	<b>Pavement Markings (Thermo), (S)</b>	3,090	SF	\$2.50	\$7,725.00
73	<b>Paint Median Nose w/ RPM(s), (S)</b>	3	EA	\$103.00	\$309.00
74	<b>Paint Curb (Red, White, or Yellow), (S)</b>	285	LF	\$1.60	\$456.00
75	<b>Type "C" Detector Loop, (S)</b>	6	EA	\$775.00	\$4,650.00
76	<b>Type "D" Detector Loop, (S)</b>	51	EA	\$250.00	\$12,750.00
77	<b>Type "E" Detector Loop, (S)</b>	117	EA	\$220.00	\$25,740.00
78	<b>SC - Splice new to existing conductors, (S)</b>	33	EA	\$21.00	\$693.00
79	<b>DLC - Detector Loop Cable, (S)</b>	2,895	LF	\$2.15	\$6,224.25
80	<b>2-Channel Detector Card, (S)</b>	13	EA	\$290.00	\$3,770.00
<b>Sub-Total: Arterial Street Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					<b>\$138,948.40</b>
<b>Minor Street Maintenance And Traffic Improvements (R-4346 and R-4351)</b>					
81	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b> (Includes variable grind when indicated)	510	LF	\$13.50	\$6,885.00
82	<b>Cold Milling, Type CM2 (Depth Varies Per Plan)</b> (Includes variable grind when indicated)	290,000	SF	\$0.21	\$60,900.00
83	<b>Cold Milling, Type CM3 (Full Depth)</b>	52,000	SF	\$1.89	\$98,280.00
84	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F)</b> (Includes all areas to receive Slurry Seal, ARAM treatment, and Cold Milling Type CM1/CM2.)	101,000	LF	\$2.43	\$245,430.00
85	<b>Crushed Aggregate Base, (F)</b>	1,070	CY	\$60.00	\$64,200.00
86	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans and slot patches.)	4,010	TONS	\$62.00	\$248,620.00
87	<b>Construct Asphalt Rubber Aggregate Membrane (ARAM) (S)</b>	2,980,000	SF	\$0.41	\$1,221,800.00
88	<b>Construct Slurry Seal, Type II</b>	2,980,000	SF	\$0.16	\$476,800.00
89	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	1,500	CY	\$33.00	\$49,500.00
90	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	500	CY	\$48.00	\$24,000.00
91	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	250	TN	\$112.00	\$28,000.00
92	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	300	EA	\$290.00	\$87,000.00
93	<b>Adjust Manhole to Grade</b> (Includes Electric, Water, Sewer, and Storm Drain manhole covers)	385	EA	\$345.00	\$132,825.00
94	<b>Concrete Curb and Gutter per City Std 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on plans.)	2,600	LF	\$53.00	\$137,800.00
95	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	1,400	LF	\$91.00	\$127,400.00
96	<b>Concrete Cross Gutter per Std 220</b> (Includes ribbon gutters and all modifications as indicated.)	4,000	SF	\$14.20	\$56,800.00
97	<b>Concrete Driveway per City Std 302.</b> (Includes all modifications as indicated.)	1,200	SF	\$13.00	\$15,600.00
98	<b>PCC Pedstrian Ramp per City Std 304.</b> (Type per plan, includes any modifications as necessary.)	275	EA	\$3,600.00	\$990,000.00
99	<b>PCC Pedstrian Ramp per City Std 304, Type VII</b>	1,450	SF	\$11.00	\$15,950.00
100	<b>PCC Sidewalk per City Std 325</b> (Includes parkway slope grading in conformance with the plans and the Standard 325. Also includes sidewalk of 6" thickness where indicated or required for the driveway approach. Includes furnishing and installing traffic rated boxes and lids when indicated)	35,000	SF	\$7.20	\$252,000.00
101	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	1,200	SF	\$11.00	\$13,200.00

102	Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)	8,835	LF	\$1.25	\$11,043.75
103	4" Solid White Stripe (Thermo) - Detail 27B, (S)	595	LF	\$0.60	\$357.00
104	8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)	65	LF	\$2.05	\$133.25
105	12" Solid Stripe White or Yellow (Thermo), (S)	6,150	SF	\$2.90	\$17,835.00
106	Pavement Legends / Markings (Thermo), (S)	4,475	SF	\$3.30	\$14,767.50
107	Type "G" Markers, (S)	17	EA	\$3.10	\$52.70
108	Type "D" Detector Loop, (S)	9	EA	\$250.00	\$2,250.00
109	Remove Sign (No Post), (S)	31	EA	\$47.00	\$1,457.00
110	Remove Sign (One Post), (S)	193	EA	\$62.00	\$11,966.00
111	Install Sign (No Post), (S)	37	EA	\$125.00	\$4,625.00
112	Install Sign (One Post), (S)	126	EA	\$256.00	\$32,256.00
113	Install Street Name Sign, (S)	123	EA	\$340.00	\$41,820.00
114	Relocate Sign (No Post), (S)	22	EA	\$125.00	\$2,750.00
115	Relocate Sign (One Post), (S)	2	EA	\$185.00	\$370.00
<b>Sub-Total: Minor Street Maintenance and Traffic Improvements (R-4346 and R-4351)</b>					<b>\$4,494,673.20</b>
<b>Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					
116	Furnish and Install 18" RCP Pipe. (Includes pre and post inspection video requirements, PWS connection at the existing RCB, and all requirements as described in the Special Provisions.)	66	LF	\$440.00	\$29,040.00
117	Construct Catch Basin per City Std 405, W=8'	1	EA	\$7,200.00	\$7,200.00
118	Construct Concrete Sidewalk per City Std 325	325	SF	\$10.30	\$3,347.50
<b>Sub-Total: Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					<b>\$39,587.50</b>
<b>Fountain Demolition and Landscape Improvements (Exhibit H)</b>					
119	Concrete / Cobble Fountain Structure Demolition (Includes all labor and equipment for demolition and proper disposal)	1	LS	\$26,000.00	\$26,000.00
120	Soil Preparation/Fine Grading	2,200	SF	\$1.80	\$3,960.00
121	Import Fill, (F). (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	175	CY	\$32.00	\$5,600.00
122	Top Soil, (F)	20	CY	\$72.00	\$1,440.00
123	Wood Mulch (2" Layer)	2,200	SF	\$0.73	\$1,606.00
124	Sod	120	SF	\$1.93	\$231.60
125	1 Gallon Drought Tolerant Plantings	130	EA	\$10.40	\$1,352.00
126	Design, Furnish & Install/Modify Irrigation System	1	LS	\$12,480.00	\$12,480.00
127	NDS atrium grate and cleanout box, 3" pvc pipes, Curb outlet, and coring.	1	LS	\$4,500.00	\$4,500.00
<b>Sub-Total: Fountain Demolition and Landscape Improvements (Exhibit H)</b>					<b>\$57,169.60</b>
<b>Bid Total</b>					<b>\$7,920,147.45</b>

<b>Subcontractor Information</b>			
<b>Subcontractor Name</b>	<b>Location</b>	<b>Portion</b>	<b>Amount</b>
American Pavement Systems	Modesto, CA	ARAM	\$1,311,880.00
Steiny & Company	Baldwin Park, CA	Electrical/Loops	\$52,799.00
Cat Tracking	Riverside, CA	Striping	\$169,851.00
EBS General Engineering	Corona, CA	Concrete	\$1,465,000.00

Global Road Sealing	Garden Grove, CA	Crack Fill	\$234,200.00
S.R.D.	Anaheim, CA	Pipe Work	\$44,180.00
All American Asphalt	Corona, CA	Slurry Seal	\$447,000.00
Phoenix Landscape	Fullerton, CA	Landscaping	\$53,363.00

# BID RESULTS

City of Riverside  
Finance Dept./Purchasing

Due Date	1/13/2016	Bid No.	7354
Before	2:00pm	Estimate	\$7,698,994.25

## Bid Description

2015/2016 Arterial and Minor Streets Maintenance

### Bidder

EBS General Engineering, Inc.

Item No.	Item Description	Qty	Unit	Unit Price	Ext. Price
<b>Incidental Items</b>					
1	<b>Note:</b> All items subject to any special notes or footnotes appearing on this Engineer's estimate included with the bid documents.	...	...	...	...
2	<b>Note:</b> The Contract lump sum or unit price for each Contract Bid Item shall include full compensation for all labor, materials, tools, taxes, profit, overhead, incidentals and appurtenant work necessary for performing and completing the work of the Contract Bid Item as required by the Project Plans, Specifications, Special Provisions and other Contract Documents. Such compensation shall also include or take into consideration any additional provisions or conditions specifically stated immediately following the Contract Bid Item.	...	...	...	...
3	<b>Note:</b> In the absence of a specific bid item or specific payment provisions for any portion of the work required by the Contract Documents, the bidder shall include the bidder's compensation for that portion of the Contract work in the Contract unit price(s) and/or lump sum price(s) of the bid item(s) that require such work, or are closely related to such work. Therefore, no separate or additional payment will be made to the Contractor for any such work on the premise that such work lacks specific bid item(s) or specific payment provisions.	...	...	...	...
4	<b>Note:</b> "(P)" adjacent to a Contract bid item designates a "Partial Pay Item" per Section 9-3.2 of the Special Provisions.	...	...	...	...
5	<b>Note:</b> "(F)" adjacent to a Contract bid item designates a Final Pay Quantity per Section 9-3.2.1 of the Special Provisions.	...	...	...	...
6	<b>Note:</b> "(S)" adjacent to a Contract bid item designates a "Specialty Item" per Section 2-3.2 of the Special Provisions.	...	...	...	...
7	<b>Mobilization for Arterial Streets &amp; Exhibit G (Bid Items 11, 15, and 19 thru 80), (P)</b>	1	LS	\$140,000.00	\$140,000.00
8	<b>Mobilization for Minor Streets (Bid Items 12, 16, and 81 thru 115), (P)</b>	1	LS	\$123,000.00	\$123,000.00
9	<b>Mobilization for Jurupa Avenue Storm Drain (Bid Items 13, 17, and 116 thru 118), (P)</b>	1	LS	\$12,000.00	\$12,000.00
10	<b>Mobilization for Exhibit H (Bid Items 14, 18, and 119 thru 127), (P)</b>	1	LS	\$3,000.00	\$3,000.00
11	<b>Water Pollution Control for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P)</b>	1	LS	\$15,000.00	\$15,000.00
12	<b>Water Pollution Control for Minor Streets (Bid Items 81 thru 115), (P)</b>	1	LS	\$10,000.00	\$10,000.00
13	<b>Water Pollution Control for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P)</b>	1	LS	\$4,500.00	\$4,500.00
14	<b>Water Pollution Control for Exhibit H (Bid Items 119 thru 127), (P)</b>	1	LS	\$2,500.00	\$2,500.00
15	<b>Traffic Control and Access for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$174,820.95	\$174,820.95
16	<b>Traffic Control and Access for Minor Streets (Bid Items 81 thru 115), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$50,000.00	\$50,000.00

17	<b>Traffic Control and Access for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$5,000.00	\$5,000.00
18	<b>Traffic Control and Access for Exhibit H (Bid Items 119 thru 127), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$3,000.00	\$3,000.00
<b>Sub-Total: Incidental Items</b>					\$542,820.95
<b>Arterial Street Maintenance (R-4336 and Exhibit G)</b>					
19	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,500	CY	\$45.00	\$112,500.00
20	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	1,300	CY	\$40.00	\$52,000.00
21	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,000	TON	\$70.00	\$140,000.00
22	<b>Unclassified Excavation for W. La Cadena Drive, (F).</b> (Includes approximately 100 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	120	CY	\$90.00	\$10,800.00
23	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b>	3,500	LF	\$5.00	\$17,500.00
24	<b>Cold Milling - Type CM2 (Depth Varies Per Plan).</b>	730,000	SF	\$0.29	\$211,700.00
25	<b>Cold Milling - Type CM3 (Full Depth).</b>	15,000	SF	\$0.50	\$7,500.00
26	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans. Includes median removals when required.)	7,200	TON	\$67.25	\$484,200.00
27	<b>Asphalt Rubber Hot Mix - Gap Graded (ARHM-GG) (0.12' min.) Overlay</b>	7,500	TON	\$76.00	\$570,000.00
28	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F).</b> (Applies to all surface treatment locations regardless if a median exists or not.)	14,000	LF	\$3.50	\$49,000.00
29	<b>Adjust Manhole Cover to Grade.</b> (Includes Electric, Telephone, Sewer, and Storm Drain manhole covers, and grate inlets.)	90	EA	\$760.00	\$68,400.00
30	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade.</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	100	EA	\$600.00	\$60,000.00
31	<b>Adjust Electric Manhole Vault Frame to Grade.</b> (Includes any adjustment/protection necessary for top to sit flush or 1/4" above finished grade. Includes proper electrical licensing.)	9	EA	\$3,900.00	\$35,100.00
32	<b>Concrete Curb and Gutter per City Std. 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on the plans.)	3,750	LF	\$35.00	\$131,250.00
33	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	210	LF	\$75.00	\$15,750.00
34	<b>Cobblestone Curb and Gutter per Part 10 of the Special Provisions</b>	500	LF	\$80.00	\$40,000.00
35	<b>Concrete Retaining Curb. (0"-18")</b>	550	LF	\$15.00	\$8,250.00
36	<b>Construct AC Berm per City Std. 250.</b> (Includes W. La Cadena Avenue and Central Avenue in locations as indicated on the plans or if necessary. Also includes hand forming where necessary.)	600	LF	\$9.00	\$5,400.00
37	<b>Concrete Cross Gutter per City Std. 220.</b> (Includes all modifications as indicated.)	5,000	SF	\$13.00	\$65,000.00
38	<b>Concrete Driveway per City Std. 302.</b> (Includes all modifications as indicated.)	10,000	SF	\$10.00	\$100,000.00
39	<b>PCC Pedestrian Ramp per City Std. 304 or Caltrans Standard Plan A88A.</b> (Type per plan, includes any modifications as necessary.)	65	EA	\$3,200.00	\$208,000.00

40	<b>PCC Sidewalk per City Std. 325.</b> (Includes parkway slope grading in conformance with City Std. 325.)	25,500	SF	\$6.50	\$165,750.00
41	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	550	SF	\$10.00	\$5,500.00
42	<b>R&amp;R Catch Basin Apron Only, per City Std. 405</b>	1	EA	\$4,000.00	\$4,000.00
43	<b>Parkway Drain per City Std. 410</b>	2	EA	\$4,000.00	\$8,000.00
44	<b>Concrete Pavement Section on Rivera Street</b>	1,150	SF	\$6.00	\$6,900.00
45	<b>Concrete Bus Pad per Detail in Special Provisions</b>	14	EA	\$17,000.00	\$238,000.00
46	<b>3.5" Thick Concrete Median</b>	25	SF	\$50.00	\$1,250.00
47	<b>Decorative White Rock for Tree Wells on Central Avenue.</b> (Includes clearing tree wells of dirt, debris, stumps, and tripping hazards.)	10	CY	\$500.00	\$5,000.00
48	<b>Crushed Rock Permeable Tree Well, (S).</b> (Includes training, all subsurface preparation, geogrids, aggregates, resins, and installation. Well sizes range from 16 SF to 54 SF. Total square footage for selected tree wells is 1600 SF. Product type must match Rockpave FlowStone "Desert Rose" from Exhibit C in Part 10 of the Special Provisions, or City approved equal.)	39	EA	\$1,000.00	\$39,000.00
49	<b>Exhibit G - Unclassified Excavation for Slope Restoration at Canyon Ridge Drive and Van Buren Blvd, (F).</b> (Includes approximately 50 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	800	CY	\$70.00	\$56,000.00
50	<b>Exhibit G - Import Fill, (F).</b> (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	375	CY	\$90.00	\$33,750.00
51	<b>Exhibit G - White Vinyl Fence.</b> (Type and color shall match existing. Includes all work to connect to existing fence as indicated on Exhibit G in Part 10 of the Special Provisions.)	25	LF	\$100.00	\$2,500.00
52	<b>Exhibit G - Hydroseed.</b> (Includes 365 days of hydroseed establishment.)	5,000	SF	\$2.00	\$10,000.00
<b>Sub-Total: Arterial Street Maintenance (R-4346 and Exhibit G)</b>					<b>\$2,968,000.00</b>
<b>Arterial Traffic Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					
53	<b>Install Sign (No Post), (S)</b>	3	EA	\$144.00	\$432.00
54	<b>Install Sign (One Post), (S)</b>	22	EA	\$297.60	\$6,547.20
55	<b>Install Street Name Sign, (S)</b>	21	EA	\$396.00	\$8,316.00
56	<b>Remove Sign, (S)</b>	29	EA	\$54.00	\$1,566.00
57	<b>4" Dashed White Stripe (Thermo) - Detail 9 w/ RPM(s), (S)</b>	21,020	LF	\$0.48	\$10,089.60
58	<b>Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)</b>	10,010	LF	\$1.45	\$14,514.50
59	<b>Detail 26 - (RPM's)</b>	400	LF	\$0.60	\$240.00
60	<b>4" Solid White Stripe (Thermo) - Detail 27B, (S)</b>	2,840	LF	\$0.45	\$1,278.00
61	<b>Double Yellow Median Island Stripe (Thermo) - Detail 29 w/ RPM(s), (S)</b>	1,210	LF	\$2.70	\$3,267.00
62	<b>Two Way Left Trun Stripe (Thermo) - Detail 32 w/ RPM(s), (S)</b>	2,765	LF	\$2.70	\$7,465.50
63	<b>Exit Ramp Neutral Area (Thermo) - Detail 36 w/ RPMs, (S)</b>	345	LF	\$1.20	\$414.00
64	<b>8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)</b>	1,925	LF	\$1.20	\$2,310.00
65	<b>8" Solid White Stripe (Thermo) - Detail 38A, (S)</b>	200	LF	\$1.05	\$210.00
66	<b>8" Solid White Stripe (Thermo) - Detail 39, (S)</b>	16,435	LF	\$0.90	\$14,791.50
67	<b>8" Solid White Stripe (Thermo) - Detail 39A, (S)</b>	2,620	LF	\$0.90	\$2,358.00
68	<b>4" Dashed White Stripe (Thermo) - Detail 40, (S)</b>	665	LF	\$2.40	\$1,596.00
69	<b>4" Solid Stripe (Thermo), (S)</b>	3,110	LF	\$1.80	\$5,598.00
70	<b>6" Solid Stripe (Thermo), (S)</b>	755	LF	\$2.40	\$1,812.00
71	<b>12" Solid Stripe (Thermo), (S)</b>	5,240	SF	\$2.30	\$12,052.00
72	<b>Pavement Markings (Thermo), (S)</b>	3,090	SF	\$3.80	\$11,742.00
73	<b>Paint Median Nose w/ RPM(s), (S)</b>	3	EA	\$120.00	\$360.00

74	Paint Curb (Red, White, or Yellow), (S)	285	LF	\$1.80	\$513.00
75	Type "C" Detector Loop, (S)	6	EA	\$900.00	\$5,400.00
76	Type "D" Detector Loop, (S)	51	EA	\$282.00	\$14,382.00
77	Type "E" Detector Loop, (S)	117	EA	\$252.00	\$29,484.00
78	SC - Splice new to existing conductors, (S)	33	EA	\$24.00	\$792.00
79	DLC - Detector Loop Cable, (S)	2,895	LF	\$2.40	\$6,948.00
80	2-Channel Detector Card, (S)	13	EA	\$336.00	\$4,368.00
Sub-Total: Arterial Street Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)					\$168,846.30
<b>Minor Street Maintenance And Traffic Improvements (R-4346 and R-4351)</b>					
81	Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth). (Includes variable grind when indicated)	510	LF	\$15.00	\$7,650.00
82	Cold Milling, Type CM2 (Depth Varies Per Plan) (Includes variable grind when indicated)	290,000	SF	\$0.27	\$78,300.00
83	Cold Milling, Type CM3 (Full Depth)	52,000	SF	\$2.05	\$106,600.00
84	Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F) (Includes all areas to receive Slurry Seal, ARAM treatment, and Cold Milling Type CM1/CM2.)	101,000	LF	\$2.30	\$232,300.00
85	Crushed Aggregate Base, (F)	1,070	CY	\$40.00	\$42,800.00
86	Asphalt Pavement - DGAC (Includes all new paving and replacement paving in areas indicated on plans and slot patches.)	4,010	TONS	\$67.00	\$268,670.00
87	Construct Asphalt Rubber Aggregate Membrane (ARAM) (S)	2,980,000	SF	\$0.45	\$1,341,000.00
88	Construct Slurry Seal, Type II	2,980,000	SF	\$0.21	\$625,800.00
89	Removal of Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	1,500	CY	\$60.00	\$90,000.00
90	Replacement Base for Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	500	CY	\$40.00	\$20,000.00
91	Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material (Includes locations not indicated on the plans, at the direction of the engineer.)	250	TN	\$70.00	\$17,500.00
92	Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade (Includes cleaning and painting all facilities and installing city furnished material as specified.)	300	EA	\$400.00	\$120,000.00
93	Adjust Manhole to Grade (Includes Electric, Water, Sewer, and Storm Drain manhole covers)	385	EA	\$400.00	\$154,000.00
94	Concrete Curb and Gutter per City Std 200. (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on plans.)	2,600	LF	\$35.00	\$91,000.00
95	Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions	1,400	LF	\$75.00	\$105,000.00
96	Concrete Cross Gutter per Std 220 (Includes ribbon gutters and all modifications as indicated.)	4,000	SF	\$13.00	\$52,000.00
97	Concrete Driveway per City Std 302. (Includes all modifications as indicated.)	1,200	SF	\$10.00	\$12,000.00
98	PCC Pedstrian Ramp per City Std 304. (Type per plan, includes any modifications as necessary.)	275	EA	\$3,300.00	\$907,500.00
99	PCC Pedstrian Ramp per City Std 304, Type VII	1,450	SF	\$10.00	\$14,500.00
100	PCC Sidewalk per City Std 325 (Includes parkway slope grading in conformance with the plans and the Standard 325. Also includes sidewalk of 6" thickness where indicated or required for the driveway approach. Includes furnishing and installing traffic rated boxes and lids when indicated)	35,000	SF	\$6.50	\$227,500.00
101	PCC Sidewalk per City Std 325, Modified (6" Thick)	1,200	SF	\$10.00	\$12,000.00
102	Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)	8,835	LF	\$1.45	\$12,810.75
103	4" Solid White Stripe (Thermo) - Detail 27B, (S)	595	LF	\$0.60	\$357.00
104	8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)	65	LF	\$2.40	\$156.00
105	12" Solid Stripe White or Yellow (Thermo), (S)	6,150	SF	\$3.30	\$20,295.00

106	Pavement Legends / Markings (Thermo), (S)	4,475	SF	\$3.80	\$17,005.00
107	Type "G" Markers, (S)	17	EA	\$25.00	\$425.00
108	Type "D" Detector Loop, (S)	9	EA	\$282.00	\$2,538.00
109	Remove Sign (No Post), (S)	31	EA	\$54.00	\$1,674.00
110	Remove Sign (One Post), (S)	193	EA	\$72.00	\$13,896.00
111	Install Sign (No Post), (S)	37	EA	\$144.00	\$5,328.00
112	Install Sign (One Post), (S)	126	EA	\$295.00	\$37,170.00
113	Install Street Name Sign, (S)	123	EA	\$396.00	\$48,708.00
114	Relocate Sign (No Post), (S)	22	EA	\$144.00	\$3,168.00
115	Relocate Sign (One Post), (S)	2	EA	\$216.00	\$432.00
<b>Sub-Total: Minor Street Maintenance and Traffic Improvements (R-4346 and R-4351)</b>					<b>\$4,690,082.75</b>
<b>Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					
116	Furnish and Install 18" RCP Pipe. (Includes pre and post inspection video requirements, PWS connection at the existing RCB, and all requirements as described in the Special Provisions.)	66	LF	\$250.00	\$16,500.00
117	Construct Catch Basin per City Std 405, W=8'	1	EA	\$4,000.00	\$4,000.00
118	Construct Concrete Sidewalk per City Std 325	325	SF	\$10.00	\$3,250.00
<b>Sub-Total: Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					<b>\$23,750.00</b>
<b>Fountain Demolition and Landscape Improvements (Exhibit H)</b>					
119	Concrete / Cobble Fountain Structure Demolition (Includes all labor and equipment for demolition and proper disposal)	1	LS	\$28,000.00	\$28,000.00
120	Soil Preparation/Fine Grading	2,200	SF	\$3.00	\$6,600.00
121	Import Fill, (F). (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	175	CY	\$50.00	\$8,750.00
122	Top Soil, (F)	20	CY	\$75.00	\$1,500.00
123	Wood Mulch (2" Layer)	2,200	SF	\$3.00	\$6,600.00
124	Sod	120	SF	\$5.00	\$600.00
125	1 Gallon Drought Tolerant Plantings	130	EA	\$15.00	\$1,950.00
126	Design, Furnish & Install/Modify Irrigation System	1	LS	\$10,000.00	\$10,000.00
127	NDS atrium grate and cleanout box, 3" pvc pipes, Curb outlet, and coring.	1	LS	\$5,000.00	\$5,000.00
<b>Sub-Total: Fountain Demolition and Landscape Improvements (Exhibit H)</b>					<b>\$69,000.00</b>
					<b>Bid Total</b>
					<b>\$8,462,500.00</b>

<b>Subcontractor Information</b>			
<b>Subcontractor Name</b>	<b>Location</b>	<b>Portion</b>	<b>Amount</b>
All American Asphalt	Corona, CA	Slurry Seal	\$492,000.00
EBS Utilies Adj	Corona, CA	Adj. Utilities	\$370,000.00
RJ Noble	Orange, CA	Grinding/Paving	\$1,400,000.00
CPE	La Puente, CA	Loops	\$53,549.00
American Pavement Systems	Modesto, CA	Rubber Aggregate	Sub Information Does Not Comply to PCC 104
Gal Stripe	Colton, CA	Striping	Sub Information Does Not Comply to PCC 104



# BID RESULTS

City of Riverside  
Finance Dept./Purchasing

Due Date	1/13/2016	Bid No.	7354
Before	2:00pm	Estimate	\$7,698,994.25

## Bid Description

2015/2016 Arterial and Minor Streets Maintenance

### Bidder

Excel Paving Company

Item No.	Item Description	Qty	Unit	Unit Price	Ext. Price
<b>Incidental Items</b>					
1	<b>Note:</b> All items subject to any special notes or footnotes appearing on this Engineer's estimate included with the bid documents.	...	...	...	...
2	<b>Note:</b> The Contract lump sum or unit price for each Contract Bid Item shall include full compensation for all labor, materials, tools, taxes, profit, overhead, incidentals and appurtenant work necessary for performing and completing the work of the Contract Bid Item as required by the Project Plans, Specifications, Special Provisions and other Contract Documents. Such compensation shall also include or take into consideration any additional provisions or conditions specifically stated immediately following the Contract Bid Item.	...	...	...	...
3	<b>Note:</b> In the absence of a specific bid item or specific payment provisions for any portion of the work required by the Contract Documents, the bidder shall include the bidder's compensation for that portion of the Contract work in the Contract unit price(s) and/or lump sum price(s) of the bid item(s) that require such work, or are closely related to such work. Therefore, no separate or additional payment will be made to the Contractor for any such work on the premise that such work lacks specific bid item(s) or specific payment provisions.	...	...	...	...
4	<b>Note:</b> "(P)" adjacent to a Contract bid item designates a "Partial Pay Item" per Section 9-3.2 of the Special Provisions.	...	...	...	...
5	<b>Note:</b> "(F)" adjacent to a Contract bid item designates a Final Pay Quantity per Section 9-3.2.1 of the Special Provisions.	...	...	...	...
6	<b>Note:</b> "(S)" adjacent to a Contract bid item designates a "Specialty Item" per Section 2-3.2 of the Special Provisions.	...	...	...	...
7	<b>Mobilization for Arterial Streets &amp; Exhibit G (Bid Items 11, 15, and 19 thru 80), (P)</b>	1	LS	\$150,000.00	\$150,000.00
8	<b>Mobilization for Minor Streets (Bid Items 12, 16, and 81 thru 115), (P)</b>	1	LS	\$130,000.00	\$130,000.00
9	<b>Mobilization for Jurupa Avenue Storm Drain (Bid Items 13, 17, and 116 thru 118), (P)</b>	1	LS	\$10,000.00	\$10,000.00
10	<b>Mobilization for Exhibit H (Bid Items 14, 18, and 119 thru 127), (P)</b>	1	LS	\$25,000.00	\$25,000.00
11	<b>Water Pollution Control for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P)</b>	1	LS	\$24,000.00	\$24,000.00
12	<b>Water Pollution Control for Minor Streets (Bid Items 81 thru 115), (P)</b>	1	LS	\$17,000.00	\$17,000.00
13	<b>Water Pollution Control for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P)</b>	1	LS	\$4,000.00	\$4,000.00
14	<b>Water Pollution Control for Exhibit H (Bid Items 119 thru 127), (P)</b>	1	LS	\$8,000.00	\$8,000.00
15	<b>Traffic Control and Access for Arterial Streets &amp; Exhibit G (Bid Items 19 thru 80), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$182,000.00	\$182,000.00
16	<b>Traffic Control and Access for Minor Streets (Bid Items 81 thru 115), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$80,000.00	\$80,000.00

17	<b>Traffic Control and Access for Jurupa Avenue Storm Drain (Bid Items 116 thru 118), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$9,000.00	\$9,000.00
18	<b>Traffic Control and Access for Exhibit H (Bid Items 119 thru 127), (P).</b> (Includes all requirements indicated in Section 7-10-1.1 of the Special Provisions which is not included in any other specific bid item.)	1	LS	\$22,000.00	\$22,000.00
<b>Sub-Total: Incidental Items</b>					\$661,000.00
<b>Arterial Street Maintenance (R-4336 and Exhibit G)</b>					
19	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,500	CY	\$72.00	\$180,000.00
20	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	1,300	CY	\$60.00	\$78,000.00
21	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material.</b> (Includes locations not indicated on the plans, at the direction of the engineer as described in Section 3-2.2.1.1 of the Special Provisions.)	2,000	TON	\$75.00	\$150,000.00
22	<b>Unclassified Excavation for W. La Cadena Drive, (F).</b> (Includes approximately 100 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	120	CY	\$78.00	\$9,360.00
23	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b>	3,500	LF	\$2.00	\$7,000.00
24	<b>Cold Milling - Type CM2 (Depth Varies Per Plan).</b>	730,000	SF	\$0.20	\$146,000.00
25	<b>Cold Milling - Type CM3 (Full Depth).</b>	15,000	SF	\$0.50	\$7,500.00
26	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans. Includes median removals when required.)	7,200	TON	\$59.00	\$424,800.00
27	<b>Asphalt Rubber Hot Mix - Gap Graded (ARHM-GG) (0.12' min.) Overlay</b>	7,500	TON	\$77.00	\$577,500.00
28	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F).</b> (Applies to all surface treatment locations regardless if a median exists or not.)	14,000	LF	\$2.30	\$32,200.00
29	<b>Adjust Manhole Cover to Grade.</b> (Includes Electric, Telephone, Sewer, and Storm Drain manhole covers, and grate inlets.)	90	EA	\$600.00	\$54,000.00
30	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade.</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	100	EA	\$500.00	\$50,000.00
31	<b>Adjust Electric Manhole Vault Frame to Grade.</b> (Includes any adjustment/protection necessary for top to sit flush or 1/4" above finished grade. Includes proper electrical licensing.)	9	EA	\$600.00	\$5,400.00
32	<b>Concrete Curb and Gutter per City Std. 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on the plans.)	3,750	LF	\$44.00	\$165,000.00
33	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	210	LF	\$134.00	\$28,140.00
34	<b>Cobblestone Curb and Gutter per Part 10 of the Special Provisions</b>	500	LF	\$115.00	\$57,500.00
35	<b>Concrete Retaining Curb. (0"-18")</b>	550	LF	\$33.00	\$18,150.00
36	<b>Construct AC Berm per City Std. 250.</b> (Includes W. La Cadena Avenue and Central Avenue in locations as indicated on the plans or if necessary. Also includes hand forming where necessary.)	600	LF	\$16.00	\$9,600.00
37	<b>Concrete Cross Gutter per City Std. 220.</b> (Includes all modifications as indicated.)	5,000	SF	\$18.00	\$90,000.00
38	<b>Concrete Driveway per City Std. 302.</b> (Includes all modifications as indicated.)	10,000	SF	\$12.00	\$120,000.00

39	<b>PCC Pedestrian Ramp per City Std. 304 or Caltrans Standard Plan A88A.</b> (Type per plan, includes any modifications as necessary.)	65	EA	\$4,000.00	\$260,000.00
40	<b>PCC Sidewalk per City Std. 325.</b> (Includes parkway slope grading in conformance with City Std. 325.)	25,500	SF	\$8.00	\$204,000.00
41	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	550	SF	\$14.00	\$7,700.00
42	<b>R&amp;R Catch Basin Apron Only, per City Std. 405</b>	1	EA	\$4,500.00	\$4,500.00
43	<b>Parkway Drain per City Std. 410</b>	2	EA	\$4,200.00	\$8,400.00
44	<b>Concrete Pavement Section on Rivera Street</b>	1,150	SF	\$21.00	\$24,150.00
45	<b>Concrete Bus Pad per Detail in Special Provisions</b>	14	EA	\$18,000.00	\$252,000.00
46	<b>3.5" Thick Concrete Median</b>	25	SF	\$50.00	\$1,250.00
47	<b>Decorative White Rock for Tree Wells on Central Avenue.</b> (Includes clearing tree wells of dirt, debris, stumps, and tripping hazards.)	10	CY	\$168.00	\$1,680.00
48	<b>Crushed Rock Permeable Tree Well, (S).</b> (Includes training, all subsurface preparation, geogrids, aggregates, resins, and installation. Well sizes range from 16 SF to 54 SF. Total square footage for selected tree wells is 1600 SF. Product type must match Rockpave FlowStone "Desert Rose" from Exhibit C in Part 10 of the Special Provisions, or City approved equal.)	39	EA	\$1,300.00	\$50,700.00
49	<b>Exhibit G - Unclassified Excavation for Slope Restoration at Canyon Ridge Drive and Van Buren Blvd, (F).</b> (Includes approximately 50 CY of unsuitable and/or excess material and debris which shall be properly disposed. Includes cumulative total of all excavation, transportation, grading, compaction, or any other methods necessary and disposal of unsuitable material to complete all work as indicated on Exhibit G in Part 10 of the Special Provisions.)	800	CY	\$57.00	\$45,600.00
50	<b>Exhibit G - Import Fill, (F).</b> (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	375	CY	\$42.00	\$15,750.00
51	<b>Exhibit G - White Vinyl Fence.</b> (Type and color shall match existing. Includes all work to connect to existing fence as indicated on Exhibit G in Part 10 of the Special Provisions.)	25	LF	\$100.00	\$2,500.00
52	<b>Exhibit G - Hydroseed.</b> (Includes 365 days of hydroseed establishment.)	5,000	SF	\$2.00	\$10,000.00
<b>Sub-Total: Arterial Street Maintenance (R-4346 and Exhibit G)</b>					<b>\$3,098,380.00</b>
<b>Arterial Traffic Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					
53	<b>Install Sign (No Post), (S)</b>	3	EA	\$125.00	\$375.00
54	<b>Install Sign (One Post), (S)</b>	22	EA	\$190.00	\$4,180.00
55	<b>Install Street Name Sign, (S)</b>	21	EA	\$300.00	\$6,300.00
56	<b>Remove Sign, (S)</b>	29	EA	\$65.00	\$1,885.00
57	<b>4" Dashed White Stripe (Thermo) - Detail 9 w/ RPM(s), (S)</b>	21,020	LF	\$0.30	\$6,306.00
58	<b>Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)</b>	10,010	LF	\$0.70	\$7,007.00
59	<b>Detail 26 - (RPM's)</b>	400	LF	\$1.00	\$400.00
60	<b>4" Solid White Stripe (Thermo) - Detail 27B, (S)</b>	2,840	LF	\$0.40	\$1,136.00
61	<b>Double Yellow Median Island Stripe (Thermo) - Detail 29 w/ RPM(s), (S)</b>	1,210	LF	\$1.15	\$1,391.50
62	<b>Two Way Left Trun Stripe (Thermo) - Detail 32 w/ RPM(s), (S)</b>	2,765	LF	\$1.35	\$3,732.75
63	<b>Exit Ramp Neutral Area (Thermo) - Detail 36 w/ RPMs, (S)</b>	345	LF	\$1.20	\$414.00
64	<b>8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)</b>	1,925	LF	\$0.90	\$1,732.50
65	<b>8" Solid White Stripe (Thermo) - Detail 38A, (S)</b>	200	LF	\$0.90	\$180.00
66	<b>8" Solid White Stripe (Thermo) - Detail 39, (S)</b>	16,435	LF	\$0.40	\$6,574.00
67	<b>8" Solid White Stripe (Thermo) - Detail 39A, (S)</b>	2,620	LF	\$0.40	\$1,048.00
68	<b>4" Dashed White Stripe (Thermo) - Detail 40, (S)</b>	665	LF	\$0.35	\$232.75
69	<b>4" Solid Stripe (Thermo), (S)</b>	3,110	LF	\$0.40	\$1,244.00
70	<b>6" Solid Stripe (Thermo), (S)</b>	755	LF	\$0.65	\$490.75

71	<b>12" Solid Stripe (Thermo), (S)</b>	5,240	SF	\$1.25	\$6,550.00
72	<b>Pavement Markings (Thermo), (S)</b>	3,090	SF	\$2.45	\$7,570.50
73	<b>Paint Median Nose w/ RPM(s), (S)</b>	3	EA	\$133.00	\$399.00
74	<b>Paint Curb (Red, White, or Yellow), (S)</b>	285	LF	\$1.05	\$299.25
75	<b>Type "C" Detector Loop, (S)</b>	6	EA	\$300.00	\$1,800.00
76	<b>Type "D" Detector Loop, (S)</b>	51	EA	\$220.00	\$11,220.00
77	<b>Type "E" Detector Loop, (S)</b>	117	EA	\$210.00	\$24,570.00
78	<b>SC - Splice new to existing conductors, (S)</b>	33	EA	\$150.00	\$4,950.00
79	<b>DLC - Detector Loop Cable, (S)</b>	2,895	LF	\$4.20	\$12,159.00
80	<b>2-Channel Detector Card, (S)</b>	13	EA	\$300.00	\$3,900.00
<b>Sub-Total: Arterial Street Improvements (XL-733, XL-734, XL-735, XL-736, and R-4336)</b>					<b>\$118,047.00</b>
<b>Minor Street Maintenance And Traffic Improvements (R-4346 and R-4351)</b>					
81	<b>Cold Milling - Type CM1 (5'-10' Wide, 0.12' Minimum Depth).</b> (Includes variable grind when indicated)	510	LF	\$5.00	\$2,550.00
82	<b>Cold Milling, Type CM2 (Depth Varies Per Plan)</b> (Includes variable grind when indicated)	290,000	SF	\$0.24	\$69,600.00
83	<b>Cold Milling, Type CM3 (Full Depth)</b>	52,000	SF	\$0.50	\$26,000.00
84	<b>Install Crack Fill/Repair Per Linear Foot of Street Centerline, (F)</b> (Includes all areas to receive Slurry Seal, ARAM treatment, and Cold Milling Type CM1/CM2.)	101,000	LF	\$2.00	\$202,000.00
85	<b>Crushed Aggregate Base, (F)</b>	1,070	CY	\$100.00	\$107,000.00
86	<b>Asphalt Pavement - DGAC</b> (Includes all new paving and replacement paving in areas indicated on plans and slot patches.)	4,010	TONS	\$61.00	\$244,610.00
87	<b>Construct Asphalt Rubber Aggregate Membrane (ARAM) (S)</b>	2,980,000	SF	\$0.50	\$1,490,000.00
88	<b>Construct Slurry Seal, Type II</b>	2,980,000	SF	\$0.18	\$536,400.00
89	<b>Removal of Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	1,500	CY	\$72.00	\$108,000.00
90	<b>Replacement Base for Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	500	CY	\$100.00	\$50,000.00
91	<b>Replacement DGAC for Unsuitable AC, Base, and/or Subgrade Material</b> (Includes locations not indicated on the plans, at the direction of the engineer.)	250	TN	\$95.00	\$23,750.00
92	<b>Adjust Gate Valve, ETS Gas Valve, or Cleanout Cover to Grade</b> (Includes cleaning and painting all facilities and installing city furnished material as specified.)	300	EA	\$400.00	\$120,000.00
93	<b>Adjust Manhole to Grade</b> (Includes Electric, Water, Sewer, and Storm Drain manhole covers)	385	EA	\$500.00	\$192,500.00
94	<b>Concrete Curb and Gutter per City Std 200.</b> (Type per plan, Curb and Gutter dimensions to match existing or as indicated for new, including any modifications indicated on plans.)	2,600	LF	\$45.00	\$117,000.00
95	<b>Pervious Concrete Gutter with Regular Concrete Curb per Part 10 of the Special Provisions</b>	1,400	LF	\$110.00	\$154,000.00
96	<b>Concrete Cross Gutter per Std 220</b> (Includes ribbon gutters and all modifications as indicated.)	4,000	SF	\$18.00	\$72,000.00
97	<b>Concrete Driveway per City Std 302.</b> (Includes all modifications as indicated.)	1,200	SF	\$13.00	\$15,600.00
98	<b>PCC Pedstrian Ramp per City Std 304.</b> (Type per plan, includes any modifications as necessary.)	275	EA	\$4,000.00	\$1,100,000.00
99	<b>PCC Pedstrian Ramp per City Std 304, Type VII</b>	1,450	SF	\$16.00	\$23,200.00
100	<b>PCC Sidewalk per City Std 325</b> (Includes parkway slope grading in conformance with the plans and the Standard 325. Also includes sidewalk of 6" thickness where indicated or required for the driveway approach. Includes furnishing and installing traffic rated boxes and lids when indicated)	35,000	SF	\$10.00	\$350,000.00
101	<b>PCC Sidewalk per City Std 325, Modified (6" Thick)</b>	1,200	SF	\$13.00	\$15,600.00

102	Double Yellow Stripe (Thermo) - Detail 22 w/ RPM(s), (S)	8,835	LF	\$0.70	\$6,184.50
103	4" Solid White Stripe (Thermo) - Detail 27B, (S)	595	LF	\$0.40	\$238.00
104	8" Solid White Stripe (Thermo) - Detail 38 w/ RPM(s), (S)	65	LF	\$0.90	\$58.50
105	12" Solid Stripe White or Yellow (Thermo), (S)	6,150	SF	\$1.25	\$7,687.50
106	Pavement Legends / Markings (Thermo), (S)	4,475	SF	\$2.45	\$10,963.75
107	Type "G" Markers, (S)	17	EA	\$4.75	\$80.75
108	Type "D" Detector Loop, (S)	9	EA	\$300.00	\$2,700.00
109	Remove Sign (No Post), (S)	31	EA	\$40.00	\$1,240.00
110	Remove Sign (One Post), (S)	193	EA	\$65.00	\$12,545.00
111	Install Sign (No Post), (S)	37	EA	\$120.00	\$4,440.00
112	Install Sign (One Post), (S)	126	EA	\$190.00	\$23,940.00
113	Install Street Name Sign, (S)	123	EA	\$300.00	\$36,900.00
114	Relocate Sign (No Post), (S)	22	EA	\$50.00	\$1,100.00
115	Relocate Sign (One Post), (S)	2	EA	\$125.00	\$250.00
<b>Sub-Total: Minor Street Maintenance and Traffic Improvements (R-4346 and R-4351)</b>					<b>\$5,128,138.00</b>
<b>Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					
116	Furnish and Install 18" RCP Pipe. (Includes pre and post inspection video requirements, PWS connection at the existing RCB, and all requirements as described in the Special Provisions.)	66	LF	\$165.00	\$10,890.00
117	Construct Catch Basin per City Std 405, W=8'	1	EA	\$6,500.00	\$6,500.00
118	Construct Concrete Sidewalk per City Std 325	325	SF	\$13.00	\$4,225.00
<b>Sub-Total: Jurupa Avenue Storm Drain Modifications at Acorn Street (D-871)</b>					<b>\$21,615.00</b>
<b>Fountain Demolition and Landscape Improvements (Exhibit H)</b>					
119	Concrete / Cobble Fountain Structure Demolition (Includes all labor and equipment for demolition and proper disposal)	1	LS	\$25,000.00	\$25,000.00
120	Soil Preparation/Fine Grading	2,200	SF	\$1.25	\$2,750.00
121	Import Fill, (F). (Includes all work and materials to furnish, deliver, and properly compact slope areas as indicated on Exhibit G in Part 10 of the Special Provisions.)	175	CY	\$43.00	\$7,525.00
122	Top Soil, (F)	20	CY	\$65.00	\$1,300.00
123	Wood Mulch (2" Layer)	2,200	SF	\$1.00	\$2,200.00
124	Sod	120	SF	\$3.00	\$360.00
125	1 Gallon Drought Tolerant Plantings	130	EA	\$12.00	\$1,560.00
126	Design, Furnish & Install/Modify Irrigation System	1	LS	\$7,500.00	\$7,500.00
127	NDS atrium grate and cleanout box, 3" pvc pipes, Curb outlet, and coring.	1	LS	\$4,000.00	\$4,000.00
<b>Sub-Total: Fountain Demolition and Landscape Improvements (Exhibit H)</b>					<b>\$52,195.00</b>
<b>Bid Total</b>					<b>\$9,079,375.00</b>

<b>Subcontractor Information</b>			
<b>Subcontractor Name</b>	<b>Location</b>	<b>Portion</b>	<b>Amount</b>
Manhole Adjusting	Pico Rivera, CA	ARAM	\$1,442,660.00
All American Asphalt	Corona, CA	Coldmill & Slurry	\$663,940.00
Global Road Seal Inc.	Garden Grove, CA	Crackseal & Loops	\$295,499.00
EBS	Corona, CA	Concrete	\$1,441,000.00

Cal Stripe	San Bernardino, CA	Striping	\$165,076.00
------------	--------------------	----------	--------------