

# **Bid No. RPU-7441**

Arlington Avenue Water Main Extension Project

## **ADDENDUM NO. 2**

**10/13/2016**

Refer to the attached pages for any questions/changes.

\*\*\* ACKNOWLEDGEMENT OF THIS ADDENDUM IS REQUIRED. Please acknowledge all addenda manually by signing and submitting all addenda cover pages as part of your final submittal before the deadline. Failure to acknowledge an addendum, unless the requirement to acknowledge has been waived, will immediately cause your bid to be deemed non-responsive.

Authorized Signature \_\_\_\_\_

(Sign here to acknowledge receipt of this addendum)

**ADDENDUM NO. 2**

**BID NO. RPU-7441**

**CITY OF RIVERSIDE PUBLIC UTILITIES DEPARTMENT**

**WATER ENGINEERING DIVISION**

**SPECIFICATION NO. 943, CONSTRUCTION DRAWINGS D5-1703061**

**ARLINGTON AVENUE WATER MAIN EXTENSION PROJECT**

Date: 10/13/16

Authorized:   
Simon K. Lee, RCE 73040

**ALL ADDENDA MUST BE ACKNOWLEDGED: BIDDER SHALL ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE PROPOSAL FORMS. ADDENDA SHALL BECOME AN INTEGRAL PART OF THE SPECIFICATIONS AND PLANS.**

**Construction Plans D5-1703061:**

- 1) Construction note “BV” of the construction plans has been amended as follow:

FURNISH AND INSTALL 16” FExFE BUTTERFLY VALVE WITH 2-MJxFE ADAPTERS PER CWD-510.

- 2) Abbreviation FxF (FLANGE BY FLANGE) on sheet 2 “ABBREVIATIONS” section of the construction plans has been amended as follow:

FExFE (FLANGE BY FLANGE)

- 3) Abbreviation MJxFE (MECHANICAL JOINT BY FLANGE) has been added to sheet 2 “ABBREVIATIONS” section of the construction plans.

- 4) Abbreviation MJxMJ (MECHANICAL JOINT BY MECHANICAL JOINT) has been added to sheet 2 “ABBREVIATIONS” section of the construction plans.

5) The following note has been added as Note 28 to the “GENERAL NOTES” section on sheet 2:

28. ANY ADDITIONAL TEMPORARY BLOW-OFFS REQUIRED SHALL BE PROVIDED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CITY.

**Bid Schedule:**

1) The following line items No. 27, 28, 29, 30, 31, and 32 have been added to Bid Schedule “A”:

<b>Item No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>Unit of Measure</b>
27	Furnish and Install a Regular Fire Hydrant with check valve and 8-inch thick concrete collar per CWD-700.	4	EA
28	Furnish and Install 8-inch MJxMJ gate valve per CWD-500.	1	EA
29	Furnish and Install 12-inch MJxMJ gate valve per CWD-500.	1	EA
30	Furnish and Install 2-inch Blow-off per CWD-411-B	1	EA
31	Furnish and Install 2-inch temporary Blow-off assembly per CWD-412.	1	EA
32	Furnish and Install 4-inch temporary Blow-off assembly per CWD-413.	1	EA

2) The following line items No. 9 and 26 have been amended to Bid Schedule “A”:

<b>Item No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>Unit of Measure</b>
9	Furnish and Install 4-inch Air Valve per CWD-460.	1	EA
26	Furnish and Install utility crossing per TYPICAL UTILITY CROSSING detail on sheet 3, including 2-inch air valve, for unforeseen crossings only. Contractor shall install utility crossing and air valve as directed by the City.	7	EA

**Special Provisions:**

1) **7-10.1 Traffic and Access. Paragraph “a” has been amended as follow:**

- a. Generally, work or reduction of the traveled way shall not be permitted prior to 8:30 a.m. nor continue after 4:00 p.m. on Arlington Avenue from Sweetwater Drive to Fairhaven Drive, and shall not be permitted prior to 8:30 a.m. nor continue after 3:30 p.m. on Arlington Avenue from Fairhaven Drive to Crestview Drive, as defined by the Public Works Department.

END