



NOT TO SCALE

Construction Notes

- 1) Provide minimum two deep water wells 4" x Min. 36" perforated PVC Pipe, filled with 3/4" crushed rock, wrapped with soil cloth.
- 2) Sand backfill may be required depending on species and location.

Approved	Date
P.V.	5/6/08
Revised	Date

Public Works Department Forestry and Landscape Division
CITY OF RIVERSIDE
PALM TREE PLANTING

Detail No.
1002