



This Section West side to extend over oil retaining wall. Construct East side duplicate of this full section.

This Section is to be same dimensions as opposite side. Compact fill and surface with 4" oil maximum to meet grade of existing paving if disturbed.

Construct galv. 2" pipe handrail from end of concrete railing to end of the existing retaining wall - approximately 40'-0". Use 3 lines 2" pipe spaced 12" above top of wall, and 12" between rails. Set posts 12" into wall and grout into line and position.