



ESTIMATE OF QUANTITIES	
Excavation	7332 cu. yds.
Conc. Curb & Gutter - Type B	3298 lin. ft.
Plant Mix Finish - 2 1/2"	73876 sq. ft.
Imported Barren	1835 cu. yds.
8" Vit. Clay Pipe & Gutter Box	139 lin. ft. - 1 box

GENERAL NOTES:
 Any relocation of existing utilities to clear the proposed work shall be the responsibility of the owner.
 Owner will install street name signs conforming to County Standard No. 28, as directed.
 All work shall conform to the requirements of the Riverside County Road Dept. specifications for the improvement of subdivision streets, dated 1955.

Co. B.M. No. 8 -
 Chiseled "X" in Sly. Cor. Conc. Sidewalk at
 NW. Cor. Rindge Road & Pierce Street.
 Elev. = 724.74

Approved: *E.D. Possible* Date 8-57
 For Riverside County
 Road Commissioner

Plan and Profile
 RINDGE ROAD
 LA SIERRA COLLEGE

J.F. Davidson RE. No. 862
 J.T. Davidson Date 8-29-57

SHEET 1 OF 2
 scales: Hor. 1" = 40'
 Vert. 1" = 4'

1669

P.B. 5-13-46