



BENCHMARK: G2-B ELEV. 771.134
 P.N. NAIL IN CENTER OF S.W. CURB RETURN AT CAMPBELL AVE. AND LA SIERRA AVE. **DESTROYED**

CONSTRUCTION BENCHMARK ELEV. 753.784
 R.R. SPIKE IN P.P. #24443J UP 12', 87' N'LY OF CAMPBELL AVE. ON MITCHELL AVE. 32' W'LY & FB. 10/21/87

THE CONTRACTOR SHALL CALL IN A LOCATION REQUEST TO UNDERGROUND SERVICE ALERT (USA), PHONE NO. 1-800-422-4133, TWO WORKING DAYS BEFORE DIGGING. NO CONSTRUCTION PERMIT ISSUED BY THE PUBLIC WORKS DEPARTMENT INVOLVING EXCAVATION FOR UNDERGROUND FACILITIES WILL BE VALID UNLESS THE APPLICANT HAS BEEN PROVIDED AN INQUIRY IDENTIFICATION NUMBER BY U.S.A.

- GENERAL NOTES**
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CLEAR THE RIGHT OF WAY IN ACCORDANCE WITH THE PROVISION OF THE LAW AS IT AFFECTS EACH UTILITY INCLUDING IRRIGATION LINES AND APPURTENANCES AND AT NO COST TO THE CITY.
 - CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF RIVERSIDE, DEPARTMENT OF PUBLIC WORKS, STANDARD DRAWING, AND THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, 1982 EDITION.
 - CONTRACTOR IS TO VERIFY EXISTING SEWER ELEVATION PRIOR TO CONSTRUCTION.
 - QUANTITIES SHOWN ARE FOR INFORMATION ONLY AND THE CITY OF RIVERSIDE IS NOT RESPONSIBLE FOR THEIR ACCURACY.
 - ALL FLAGGED ELEVATIONS SHALL BE STAKED IN THE FIELD BY THE PRIVATE ENGINEER.
 - A PLUG SHALL BE INSTALLED AND WILL REMAIN IN PLACE WHERE THE NEW SEWER CONNECTS WITH THE EXISTING SEWER UNTIL THE NEW SEWER IS ACCEPTED BY THE CITY.
 - THE PRIVATE ENGINEER SIGNING THE PLANS IS RESPONSIBLE FOR ASSURING THE ACCURACY AND ACCEPTABILITY OF THE WORK HEREON. IN THE EVENT OF DISCREPANCIES ARISING DURING CONSTRUCTION, THE PRIVATE ENGINEER SHALL BE RESPONSIBLE FOR DETERMINING AN ACCEPTABLE SOLUTION AND REVISING THE PLAN FOR APPROVAL BY THE CITY.
 - SEWER / WATER MAIN CLEARANCE SHALL COMPLY WITH CITY WATER DIVISION STDS. C.W.D. 021 AND 022.
 - NO FINISHED FLOOR ELEVATION SHALL BE LESS THAN 4' ABOVE THE SEWER FLOW LINE AT POINT OF CONNECTION WITHOUT HAVING A PROPER BACKWATER VALVE INSTALLED IN THE LATERAL.
 - ANY TRAFFIC CONTROL STRIPING OBLITERATED AND/OR BADLY WORN DURING CONSTRUCTION SHALL BE RESTORED BY THE CONTRACTOR WITHIN FIVE DAYS AFTER NOTIFICATION FROM THE CITY INSPECTORS.
 - THE SEWER CONTRACTOR SHALL ADJUST MANHOLES TO FINAL GRADE AFTER PAVING IS COMPLETED.
 - THE PRIVATE ENGINEER PREPARING THESE PLANS SHALL BE RESPONSIBLE FOR PRESERVING OR RE-ESTABLISHING AND REFERENCING SURVEY MONUMENTS DESTROYED, DISTURBED OR BURIED AS A RESULT OF CONSTRUCTION SHOWN HEREON.



ESTIMATE OF QUANTITIES

| | |
|---|----------|
| 1. 8" V.C.P. | 860 L.F. |
| 2. MANHOLE PER STD. 500 | 3 EA. |
| 3. SEWER LATERAL PER STD. 562 (4" V.C.P.) | 3 EA. |

APPROVED BY: *[Signature]* DATE: 12-15-83
 SOUTHERN CALIF. GAS CO.
 APPROVED BY: *[Signature]* DATE: 12-28-83
 IRRIGATION SYSTEM MANAGER
 WATER DIVISION
 APPROVED BY: *[Signature]* DATE: 12-28-87
 LYNN A. TERRY & ASSOCIATES
 315 SERRANO DR.
 CORONA, CA. 91720 (714) 735-6650
 LYNN A. TERRY R.C.E. 19640 DATE

CITY OF RIVERSIDE, CALIFORNIA
 PUBLIC WORKS DEPARTMENT

SEWER PLAN AND PROFILE
PARCEL MAP 18835
 CAMPBELL AVENUE, WESTERNLY
 FROM MITCHELL AVE. TO STA. 8+30

APPROVED BY: *[Signature]* DATE: 1/2/88
 PRINCIPAL ENGINEER
 PARK DEPARTMENT
 TRAFFIC DIVISION
 CHIEF PUB. WKS. ENGR. DATE: 1/2/88

APPROVED BY: *[Signature]* DATE: 1/2/88
 DIRECTOR OF PUBLIC WORKS

WORKS UP ACCOUNT No. DRAWING NUMBER **S-1341** SHEET 1 OF 1

SCALE: HORIZ. 1"=40', VERT. 1"=4'