



QUANTITY ESTIMATE

8" Vitrified Clay Pipe	988 lin. ft.
4" Vitrified Clay Pipe	604 lin. ft.
8" x 4" Wyes	18
Std. #500 Manholes	2
Std. #560 Cleanouts	2

BENCH MARK
 Spike and Lead in N.E. curb return Arlington & Palomar Way. Elev. 797.78. FB 1911A*/64.

GENERAL NOTES:
 House Connection Wyes shall be field located.
 Construction shall be in accordance with Specifications of the City of Riverside, Department of Public Works.

REVISIONS		CITY OF RIVERSIDE CALIFORNIA DEPARTMENT OF PUBLIC WORKS	
MARK	DATE	DESCRIPTION	
①	10/22/60 C.F.R.	Rev. 4" V.C.P. Fr. 554 to 604 I.P.	

**CORONADO WAY
SANITARY SEWER DISTRICT**

**CORONADO WAY
GRANADA AVENUE**

DESIGNED BY REC	CHECKED BY E. J. Will RE-9776	APPROVED BY <i>[Signature]</i> DIRECTOR OF PUBLIC WORKS
DRAWN BY REC	RECOMMENDED BY <i>[Signature]</i> ASSISTANT CITY ENGINEER	DATE 5/18/60

5-191
SHEET 1 OF 1

PROFILE

SUBMITTED	2/14/59	BY		DATE	
NOTE BOOK GRADES CHECKED		REC		2-2-59	
NO. 11167		BY			
ENGINEER					

PLAN

SUBMITTED	2/14/59	BY		DATE	
NOTE BOOK ALIGNMENT CHECKED		REC		2-2-59	
NO. 11167		BY			
ENGINEER					