



QUANTITY ESTIMATE

8" Vitrifed Clay Pipe	6135 L.F.
4" Vitrifed Clay Pipe	617 L.F.
8" x 4" Wyes	20 EA.
Manhole - Std. No. 500	4 EA.

GENERAL NOTES:

- It shall be the responsibility of the Contractor to clear the right of way in accordance with the provisions of law as it affects each utility including irrigation lines and easements and at no cost to the City.
- Construction shall be in accordance with the City of Riverside, Department of Public Works, Specification No. 461 and Standard Drawings.
- Joints in vitrifed clay pipe sewer shall conform to A.S.T.M. Standard C-425-60T, or the latest revision thereof.
- Pipe shall be bedded per Case II, Standard Drawing No. 452, unless otherwise specified on plan.
- Location of wyes and laterals to be determined in the field.
- Prior to construction of sewer, Contractor is to expose existing sewer and contact Engineer for verification of existing elevations.
- Contractor shall keep an accurate record of the stationing of all house laterals & wyes for the City of Riverside Public Works Dept. and shall mark the curbs at all laterals.
- 8" OR PER 5-338 Wedge-1ok, Speed Seal or equal, conforming to requirement of A.S.T.M. C-425-60T, pipe shall be used throughout construction.
- Portions of sewer that can not be visually inspected shall be bedded.

PROFILE

NO. 1	SUBMITTED	DATE
NO. 2	PLATED	DATE
NO. 3	GRADES CHECKED	DATE
NO. 4	SALES AND CONTRACTS OK'D.	DATE

PLAN

NO. 1	SUBMITTED	DATE
NO. 2	PLATED	DATE
NO. 3	ALIGNMENT CHECKED	DATE
NO. 4	IF OF WORK CHECKED	DATE

REVISION	
MARK	DESCRIPTION

DATE	Dec. 1963	SCALE	1" = 50'
DRAWN	B.E.L.	W.O.	63-256
CHECKED	ROU W. 4/17	F.B.	498
APPROVED BY		DATE 7-17-64	
CITY OF RIVERSIDE, CALIFORNIA		DIRECTOR OF PUBLIC WORKS	
DEPARTMENT OF PUBLIC WORKS		NO. S-456	
SEWER PLAN & PROFILE		SHEET 1 OF 1	
INTERVALE DRIVE			
TRACT No. 2766			

ALBERT A. WEBB ASSOCIATES
 CIVIL ENGINEERS - RIVERSIDE, CALIFORNIA
 APPROVED [Signature] DATE 12-31-63

As built 12/24/64 B.E.