



QUANTITY ESTIMATE Z.C. No. R-32-656

Manhole Standard No. 500	4 EA
Cleanout Standard No. 560	1 EA
8" Vitrified Clay Pipe	1,154 L.F.
Pavement Replacement	
6" Vitrified Clay Pipe	172 L.F.
Pavement Replacement	100 S.F.

QUANTITY ESTIMATE Z.C. No. R-47-690

6" Vitrified Clay Pipe	43 L.F.
------------------------	---------

Approved By  
*Albert A. Webb* 7-7-70  
 General Superintendent & Chief Engineer, N.E. & P.E. DATE

ALBERT A. WEBB ASSOCIATES  
 CIVIL ENGINEERS  
 RIVERSIDE, CALIFORNIA  
 APPROVED BY *Earl N. Wiley* DATE 1/3/66  
 R.E. No. 9876

DESIGNED BY	BEI
DRAWN BY	BEI
CHECKED BY	DA

CITY OF RIVERSIDE, CALIFORNIA  
 DEPARTMENT OF PUBLIC WORKS  
 APPROVED BY *W. J. ...* DATE 4-7-66  
 OFFICE ENGINEER  
 PARK DEPARTMENT  
 TRAFFIC DIVISION  
 ASSISTANT CITY ENGINEER

SEWER PLAN & PROFILE  
 CORRELL STREET  
 EASEMENT No. R-32-656  
 No. R-47-690  
 No. 1085  
 Correll Street, between Jurupa Ave. & Stearns St., R.R. Easement, between Stearns St. & Correll St.  
 PROJECT NO. S-654  
 SHEET 1 OF 1  
 FILE NO. 65-344-B

\* CG built 9/30/70 - norm  
 ✓ 10/15/70 - KARL

BENCH MARK:  
 PK nail in S.W. curb of Jurupa 15' West of B.C. of S.W. curb  
 return at Stearns & Jurupa, Elev. 785.10, Per C.M. P.B. 401/67

Joints shall be in accordance to A.S.T.M. Specification C-425-64  
 Type 1 or III or C-594-64T (Bong Seal) with certain exceptions  
 or Modifications on file with the City Engineer.

of the Owner. at the direction

Note: Contractor shall replace all plants, shrubs, etc. in the South line of lot 44 which may be disturbed by sewer construction.