



- GENERAL NOTES -**
1. Bench Mark 1 P.K. Nail in curb at NW Cor Third St & Chicago Ave. per P.S. 89384 (City Datum).
 2. All work shall be done in accordance with these plans, Standard Specifications No. 461, and the Standard Drawings of the City of Riverside, Dept. of Public Works.
 3. It shall be the responsibility of the contractor to clear the right of way in accordance with the provisions of the law, as it affects such utility including irrigation lines and appurtenances, and at no cost to the City of Riverside.
 4. Prior to final submittal and final cost estimate, the contractor shall submit a work order, before relocation work begins.
 5. The amount of asphalt overlay on curb and gutter has been estimated by the Engineer to be approximately 20.2 tons.
 6. The final subgrade shall have a compaction of not less than 90% for a depth of 0.5 feet as determined by test method No. 201.216 immediately prior to the placement of the cover.

S.R. 252 R-568
GARNER, TEE, TRACADAS & TROY
 CIVIL ENGINEERING - LAND SURVEYING
 357 WEST SECOND STREET
 SAN BERNARDINO, CALIFORNIA
 FRANK TRACADAS R.C.E. NO. 11447
 DATE 1-4-66

REVISIONS			CITY OF RIVERSIDE, CALIFORNIA DEPARTMENT OF PUBLIC WORKS
MARK	DATE	DESCRIPTION	
△	2-21-66	Raised 18" R.C.P. 36" dia. storm drain to match city datum.	PLAN & PROFILE KANSAS AVE. FROM THIRD ST. 269 FEET SOUTHERLY THIRD ST. FROM FRANKLIN AVE. TO KANSAS AVE. R-29-656 & R-5947

DESIGNED BY	SUBMITTED BY	APPROVED BY	PROJECT NO. 55 297
DRAWN BY	PARK DEPT. TRAFFIC DIV.	<i>J. P. ...</i>	R-1119
CHECKED BY	RECOMMENDED BY	DIRECTOR OF PUBLIC WORKS	DATE Jan 27, 1966