



GENERAL NOTES AND LEGEND

1. CONSTRUCTION TO BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, 1973 EDITION AND CITY OF RIVERSIDE STANDARD DRAWINGS.
 2. REMOVE EXISTING DEPRESSION AND REPLACE WITH FULL HEIGHT CURB AS PER STANDARD DRAWING NUMBER 303.
 3. CONSTRUCT NEW CURB DEPRESSION AS PER STANDARD DRAWING NUMBER 303 AND 304.
 4. RELOCATE MAIL BOXES TO BEHIND CURB. IN CURB SIDEWALK AREA; LEAVE 6" DIAMETER HOLE IN CONCRETE.
 5. TRIM TREE BRANCHES IN ACCORDANCE WITH STANDARD SPECIFICATIONS.
 6. CONSTRUCT DRIVEWAY APPROACH AS PER STANDARD DRAWING NUMBER 302 AND DIMENSIONS SHOWN ON PLANS.
- CONSTRUCT P.C.C. SIDEWALK, APPROACH, OR CURB AND GUTTER.
 PLACE A.C. 2" THICK.
 GRADE DIRT DRIVEWAY.
 CONNECT WALKWAY TO SIDEWALK, CONSTRUCT 2 STEPS.
 CONSTRUCT SIDEWALK AS PER STANDARD DRAWING NUMBER 305.
7. RELOCATE LAMP WISES SHOWN ON PLAN.
 8. CHECK FRAME FORMS IF NECESSARY OR REPLACE WITH LONGER FORMS.
 9. REPLACE P.C.C. 6" FILLBOX COVER WITH STEEL COVER IF IN DRIVEWAY APPROACH, ADJUST ALL OTHER 6" P.C.C.
 10. CONSTRUCT WHEELCHINE CAMPS AS PER STD. DWG. NO. 804.

FE 991-A

CITY OF RIVERSIDE PUBLIC WORKS DEPARTMENT 11-24-75	RUTLAND AVE. SIDEWALK PHILBIN AVE. TO ARLINGTON	R-1826 40
--	--	---------------------