



CONSTRUCTION NOTES
 1. REMOVE EXISTING CURB & GUTTER AND CONSTRUCT NEW. RIV. STD. NO. 10B.
 2. REMOVE EXISTING CROSS GUTTER AND CONSTRUCT NEW.
 3. REMOVE EXISTING CATCH BASIN AND CONSTRUCT TWO NEW CBS.
 4. REMOVE SIGNAL POLES, TREES AND OBSTRUCTIONS BY OTHERS.
 5. CONSTRUCT CURB RETURNS AND APRONS AS SHOWN.
 6. CONSTRUCT S SIDEWALK.
 7. CATCH BASIN, OUTLET STRUCTURE & DRAIN LINE INSTALLATION TO BE DONE BY CITY.

NOTES
 ALL DUCT FIELD GALVANIZED OR LINED OTHERWISE.
 ALL STANDARDS PROVIDED WITH PUSH BUTTONS.
 ALL WORK TO BE DONE AT EXPIRE OF OWNER'S SCHEDULE THE FOLLOWING:
 1. COST OF PURCHASE & ERECTION OF ARM SIGNAL STANDARD.
 2. COST OF LABOR IN CONSTRUCTION OF CATCH BASIN.
 3. MATCHING EXISTING PAVEMENT CURB & GUTTER.
 UTILITIES NOT SHOWN (ELEC. GAS WATER TREES NOT SHOWN) PERMITS TO BE OBTAINED BEFORE REMOVAL.
 DRIVEWAY PERMITS REQ'D BEFORE ACTION IN FIELD.
 SIDEWALKS NOT SHOWN. SIDEWALKS REQUIRED BY CITY.

REVISIONS			CITY OF RIVERSIDE DEPARTMENT OF PUBLIC WORKS
MARK	DATE	DESCRIPTION	
3-20-58		DIV. APPROACHES SHOWN	VICTORIA AVENUE CURB, GUTTER, SIDEWALK & DRAINAGE PLAN
4-4-58		NOTE ADDED	
5-15-58		EXTENDED C&G	

DESIGNED BY R. TAKU	CHECKED BY [Signature]	APPROVED BY [Signature] DIRECTOR OF PUBLIC WORKS	DATE MAY 1, 1958
------------------------	---------------------------	--	---------------------