



QUANTITY ESTIMATE

Std. Curb & Gutter	1865 lin. ft.
2 1/2" P.M.S. f seal coat	23425 sq. ft.
Concrete Cross Gutter	600 sq. ft.
Std. Catch Basin No. 140-D	3
Outlet Box	1
16" I.D. double wall 2000D concrete pipe	65 lin. ft.
36" I.D. double wall concrete pipe	15 lin. ft.
1 concrete headwall (rainf.)	1 cu. yd.

CURB RETURN DATA

No.	R.	Δ	T	L
①	27'	70°07'23"	18.95	33.04
②	27'	103°41'10"	34.36	48.86
③	27'	51°57'30"	13.16	24.48
④	27'	36°23'20"	8.88	17.16

ALBERT A. WEBB ASSOCIATES CIVIL ENGINEERS
 APPROVED *Albert A. Webb* DATE 7/3/58
 CITY OF RIVERSIDE, CALIFORNIA
 DEPARTMENT OF PUBLIC WORKS
 STREET PLAN & PROFILE
 HAWARDEN DRIVE &
 OLEANDER COURT
 OLEANDER HILLS
 HORIZ. SCALE 1"=50' VERT. SCALE 1"=5'
 APPROVED BY *W. M. ...*
 DIRECTOR OF PUBLIC WORKS
 NO. R-203
 DATE July 1958 SHEET 1 OF 1

PROFILE

NO. 392	DATE 7/3/58
BY R.E.C.	DATE 7/3/58
BY R.E.C.	DATE 7/3/58

PLAN

NO. 392	DATE 7/3/58
BY R.E.C.	DATE 7/3/58
BY R.E.C.	DATE 7/3/58