



- NOTES:**
- CONSTRUCTION TO BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION 1978 EDITION, AND CITY OF RIVERSIDE STANDARD DRAWINGS.
 - WHERE NEW CONSTRUCTION IS INDICATED, CLEAR & GRUB.
 - UTILITY REQUIRE RELOCATION SHALL BE SET PER STD DWG. NO. 200.
 - RANGE EXISTING MINIMUMS TO GRADE IN AREA OF CONSTRUCTION. REMOVE & SALVAGE EXISTING GUARD RAIL.
 - TRANSPLANT (4) CLASS III PINE TREES PER INSTRUCTIONS. SEE TITLE SHEET FOR LOCATION OF TRANSPLANTS. REMOVE CHAIN LINK FENCE, DISCONNECT PUMPS AND SALVAGE AND PLUG IRR LINE. ELECTRICAL SERVICE TO BE DISCONNECTED BY C/R PUBLIC UTILITIES.
- (200) CONSTRUCT CURB & GUTTER PER STD DWG 200.
 - (220) CONSTRUCT CROSS GUTTER SPANDREL PER STD DWG 220.
 - (230) CONSTRUCT AC BEEM PER STD DWG 230.
 - (304) CONSTRUCT WHEEL CHAIR RAMP DEPRESSIONS PER STD 304.
 - CONSTRUCT NEW STRUCTURAL SECTION: 0.55' OVER NATIVE (VAN BUREN) 0.35' OVER NATIVE (LINCOLN)
 - OVERLAY A VARIABLE THICKNESS OF AC TO STREET E.

CITY OF RIVERSIDE PUBLIC WORKS DEPARTMENT		VAN BUREN BLVD. WIDENING SOUTHWESTERLY SIDE LINCOLN AVE TO 800' NBY		ACCOUNT NO. 2002-27107
APPROVED BY PRINCIPAL ENGINEER DATE DEPARTMENT 12/2/77	APPROVED BY PUBLIC WORKS DIRECTOR DATE 3/6/78	R2048		SHEET 1 OF 1
DESIGNED BY DRAWN BY	CHECKED BY	DATE 3/6/78		FILE NO.

