



1. CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF RIVERSIDE STD. DWGS. AND STD. SPECS FOR PUBLIC WORKS CONSTRUCTION, 1982 EDITION.
- 200 - CONSTRUCT CONC. CURB & GUTTER PER STD. DWG. NO. 200.
- 220 - CONSTRUCT CONC. CROSS GUTTER PER STD. DWG. NO. 220.
- 300 - CONSTRUCT CONC. DRIVEWAY APPROACH PER STD. DWG. NO. 302.
- 304 - CONSTRUCT CONC. WHEELCHAIR RAMP PER STD. DWG. NO. 304.
- 1 - REMOVE 2"± OF DETERIORATED PAVEMENT AND REPLACE WITH 2 1/2" A.C. OVER 4" CLASS 2 BASE
- + PROP. LOCATION FOR TREES
- 500 - PLANT STREET TREES PER PARK AND RECREATION DEPARTMENT STANDARDS. CONTACT PARK PROJECT INSPECTOR AT 787-7223 PRIOR TO DIGGING PLANTING HOLES FOR APPROVAL OF PLANT MATERIAL AND TREE LOCATIONS.

<b>CITY OF RIVERSIDE</b> PUBLIC WORKS DEPARTMENT		<b>HOLDING STREET WIDENING ORANGE TO MULBERRY</b>		ACCOUNT NO. 15-550-597-1
APPROVED BY <i>[Signature]</i> PRINCIPAL ENGINEER		APPROVED BY <i>[Signature]</i> PUBLIC WORKS DIRECTOR		R-2619
DATE 11/3/85		DATE 11/3/85		SHEET 1 OF 1
DESIGNED BY <i>[Signature]</i>		DRAWN BY <i>[Signature]</i>		HORIZ. SCALE: 1" = 20' VERT. SCALE: 1" = 4'
CHECKED BY <i>[Signature]</i>		DATE 11/3/85		