



- CONSTRUCTION NOTES**
- All trees and shrubs to be removed and relocated by CIR Park Department.
  - All water meters to be relocated by CIR Public Utilities Department.
  - CIR Forces to remove all C&G southerly from Sta. G+26.83 and all exist 5' walk southerly from Curb Sta. 0+33.52 and Sta. 1+15.64.
  - CIR Forces to saw cut exist walk, Riverside City Schools Contr. to begin new walk const. by installing an expansion joint and matching exist. walk. CIR STD. DWG. NO. 325.
  - CIR Forces to saw cut exist C&G, Riverside City Schools Contr. to begin new C&G const. by installing an expansion joint and matching exist. C&G. CIR STD. DWG. NO. 200. Exist sidewalk grade at Curb Sta. 0+33.52 and Sta. 1+15.64 to be matched by new curb grade.
  - CIR Forces to remove entire exist. driveway, Riverside City Schools Contr. to const. new driveway CIR STD. NO. 302.
  - Riverside City Schools Contr. to const. new C&G and walk. CIR STD. DWG. NO. 325 C&G. CIR Forces to remove and dispose of all Asph. Conc. Paving behind new curb alignment.
  - Riverside City Schools Contr. to shape new const. C&G const. for smooth transition into exist driveway.
  - Suitable excavated material to be stock piled and used by CIR Forces as backfill following C&G and walk const.
  - Street Area of Cul-de-Sac, where pav. does not exist, shall be excavated by CIR Forces to a depth to allow for the const. of a 6" aggregate base by CIR Forces and Const. of 2 1/2" Asph. Conc. Pavt. by Riverside City Schools Contr. New Asph. Conc. Pavt. to be feathered into exist pavt. for smooth transition and crown.
  - Work on installing drain outlets by Riverside City Schools Contr. to be coordinated with contractor on Washington St.

