



NOTE TO CONTRACTOR
The existence and location of any underground utility pipes or structures shown on these plans are obtained by a search of the available records. To the best of our knowledge there are no existing lines except as shown on these plans. The contractor is required to take due precautionary measures to protect the utility lines shown and any other lines not of record or not shown on these plans.

STREET NAME SIGN SCHEDULE

A	CARLO DRIVE	6400
	BETTY DRIVE	4900

Signs of Post #2 to be furnished and installed as per City Std. Dwg. #662.

QUANTITY ESTIMATE

Std. 200 Curb & Gutter w/6" c.f.	345 lin. ft.
Std. 350 sidewalk	1,739 sq. ft.
2 1/2" AC w/ Seal Coat	6,140 sq. ft.
(10") Impacted Base Material	189 cu. yd.
Std. 180 Barricade	1 ea.
2"x4" Redwood Header	263 lin. ft.
Std. 250 - Beam	18' lin. ft.

BENCH MARK Elev. 767.38
Spike in lead in NW. cor. of Storm drainage M.H. at S.E. cor. of Street & Daway.

- GENERAL NOTES:**
- Construction to be in accordance with Standards and Specifications No. 461 of the City of Riverside, Dept. of Public Works.
 - Trim edge of existing paving where new paving joins existing pavements to clean, straight line. Construct match-up paving as shown and overlay existing paving as directed in the field to produce a smooth crown section.
 - Construction in the vicinity of the Riverside Water Co. pipeline shall be done to meet the requirements of the Riverside Water Co. and the City of Riverside, Dept. of Public Works. It shall be understood that the Riverside Water Co. shall have the opportunity of testing the line after grading & installation of base course and prior to the placing of any A.C. The cost of repairs to the pipeline caused by damage during construction shall be borne by the Contractor.
 - Prime coats and paint under are required.

Approved July 24, 1963
City of Riverside Irrigation Division
By *Albert A. Webb*
Chief, Supv. District Engr., Water Dept.

ALBERT A. WEBB ASSOCIATES
CIVIL ENGINEERS - RIVERSIDE, CALIFORNIA
APPROVED *Albert A. Webb* DATE 6/18/63
No. 3876

CITY OF RIVERSIDE, CALIFORNIA
DEPARTMENT OF PUBLIC WORKS

CARLO DRIVE
BETTY DRIVE
Carlo Dr. bet. Sunnyside Dr. & Betty Dr. West of Carlo Dr.
R/S No. G4B

DATE: 7-31-63
SCALE: 1"=50'
DRAWN: W.D. 01-318
CHECKED: ADD W.D. 372/67
APPROVED BY: *Albert A. Webb*
DIRECTOR OF PUBLIC WORKS
NO. R-716
SHEET 1 OF 1



PROJECT: CARLO DRIVE
SHEET NO. 1
DATE: 7-31-63

PLAN: CARLO DRIVE
SHEET NO. 1
DATE: 7-31-63