





SIGNING AND STRIPING GENERAL NOTES:

- SIGNING AND STRIPING INSTALLATIONS SHALL CONFORM TO THE 2014 CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (CA MUTCD), THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION (CALTRANS) STANDARD PLANS AND SPECIFICATIONS DATED 2018, AND ALL ADDENDUMS THEREON, AND THE CITY OF RIVERSIDE PUBLIC WORKS DEPARTMENT STANDARD DRAWINGS, CURRENT EDITION.
- ALL STRIPING, MARKINGS, AND LEGENDS SHALL BE REFLECTORIZED THERMOPLASTIC UNLESS OTHERWISE NOTED. THE CONTRACTOR SHALL PROVIDE AND INSTALL RAISED PAVEMENT MARKERS FOR ALL STRIPING. STRIPING, MARKINGS AND LEGENDS SHALL CONFORM TO THE LATEST CALTRANS STANDARD PLANS A20A THRU A20D AND A24A THRU A24E.
- PRIOR TO FINAL ACCEPTANCE OF STREET IMPROVEMENTS, ALL PAVEMENT STRIPING AND STENCILING WITHIN THE PERIMETER OF THE CONSTRUCTION AREA SHALL BE RESTORED TO LIKE NEW CONDITION, IN A MANNER MEETING THE APPROVAL OF THE CITY OF RIVERSIDE.
- THE CONTRACTOR SHALL RE-STRIP EXISTING STRIPING AND CURB MARKINGS OBLITERATED BY NEW CONSTRUCTION, WHETHER OR NOT SHOWN ON THE PLANS FOR REPLACEMENT, AT NO COST TO THE CITY.
- AT LOCATIONS WHERE EXISTING PAINTED CURB IS TO BE RECONSTRUCTED, THE CONTRACTOR SHALL PAINT THE NEW CURB AS SHOWN ON THE PLANS WITHIN 10 WORKING DAYS OF CURB CONSTRUCTION OR AS DIRECTED BY ENGINEER. THE PAINT SHALL BE WATER-BASED WITH 2-YEAR GUARANTEE AGAINST COLOR FADING. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT TO THE CITY WRITTEN PROOF OF THE MANUFACTURER'S 2-YEAR GUARANTEE.
- ALL NEW STRIPING SHALL BE "CAT TRACKED" AND APPROVED BY THE ENGINEER PRIOR TO FINAL INSTALLATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AFTER COMPLETING LAYOUT AND AT LEAST 3 WORKING DAYS BEFORE COMMENCING INSTALLATION OF STRIPING, MARKINGS AND MARKERS.
- TRAFFIC SIGN FACE SHALL BE 3M DIAMOND GRADE DG3 REFLECTIVE SHEETING (ASTM XI) OR APPROVED EQUAL WITH PROTECTIVE GRAFFITI OVERLAY FILM OR AS OTHERWISE NOTED. ALL WARNING SIGNS SHALL HAVE A FLUORESCENT YELLOW-GREEN BACKGROUND AND SCHOOL SIGNS NOTED SHALL HAVE A FLUORESCENT YELLOW-GREEN BACKGROUND.
- SIGNS SHALL BE STANDARD SIZE UNLESS NOTED OTHERWISE. PRIOR TO INSTALLATION, NEW SIGNS SHALL BE APPROVED BY THE CITY OF RIVERSIDE. EXACT LOCATIONS OF SIGNS SHALL BE DETERMINED BY THE CITY ENGINEER.
- ALL EXISTING SIGNS AND POSTS TO BE REMOVED SHALL BE DELIVERED TO THE CITY OF RIVERSIDE SIGN DEPARTMENT.
- WHEN PAINT IS SPECIFIED, TRAFFIC STRIPES AND MARKINGS SHALL BE APPLIED IN TWO COATS. A MINIMUM OF SEVEN DAYS SHALL BE PROVIDED BETWEEN FIRST AND SECOND COATS.
- STRIPING SHALL BE APPLIED WITHIN 48 HOURS OF SURFACE COURSE REPLACEMENT ON STREETS OPEN TO THE PUBLIC. IN NO CASE SHALL A NEWLY PAVED STREET OPEN TO THE PUBLIC BE LEFT UNSTRIPED OVER A WEEKEND OR HOLIDAY.
- CONTRACTOR SHALL INSTALL NEW SIGN(S) AND/OR POST(S) PER CITY OF RIVERSIDE STANDARD DRAWING No. 664. SEE SPECIFICATIONS. CONTRACTOR SHALL INSTALL NEW STREET NAME SIGNS AND POST PER CITY OF RIVERSIDE STANDARD DRAWING No. 662, SEE SPECIFICATIONS.
- ALL CONFLICTING STRIPING, PAVEMENT MARKINGS, LEGENDS, AND RAISED PAVEMENT MARKERS SHALL BE REMOVED EVEN IF NOT SHOWN ON PLANS. REMOVALS OF PAINTED STRIPING, PAVEMENT MARKINGS AND LEGENDS SHALL BE DONE BY WET SANDBLASTING. REMOVALS OF THERMOPLASTIC STRIPING, PAVEMENT MARKINGS AND LEGENDS SHALL BE REMOVED BY WET SANDBLASTING, GRINDING OR OTHER APPROVED METHOD AND SHALL NOT DAMAGE THE PAVEMENT. "BLACK OUT" OF EXISTING DELINEATION IS NOT PERMITTED. ALL DAMAGED PAVEMENT DUE TO REMOVALS SHALL BE REPAIRED AS NECESSARY TO MAINTAIN A SMOOTH AND UNIFORM SURFACE OR AS DIRECTED BY THE ENGINEER. ALL STRIPING REMOVALS AND LEGENDS SHALL BE "FOG SEALED".
- WHERE APPLICABLE, OUTBOUND LANE LINE DETAILS SHALL COMMENCE AT THE CROSSWALK, MEANING THE PAINTED PORTION OF THE DETAIL SHALL JOIN THE CROSSWALK.




SEE STANDARD DWG NO. 670 FOR TYPE "D" LOOP CONFIGURATION



SEE STANDARD DWG NO. 670 FOR TYPE "D" LOOP CONFIGURATION

ROADSIDE SIGNS (STANDARD SIZE):



SIGNING AND STRIPING LEGEND:

- E EXISTING TO REMAIN.
- ME MATCH EXISTING STRIPING.
- SC SPLICE TO EXISTING CONDUCTORS.
- I INSTALL LOOP DETECTOR AS NOTED ON PLAN.
- # INSTALL CALTRANS STRIPING DETAIL PER NUMBER NOTED, INCLUDING INSTALLATION OF RAISED PAVEMENT MARKERS.
- PM INSTALL PAVEMENT MARKING OR ARROW AS NOTED.
- RP REMOVE ALL EXISTING CONFLICTING TRAFFIC STRIPING AND MARKINGS AS NOTED, INCLUDING RAISED PAVEMENT MARKERS.
- RR REMOVE AND REPLACE EXISTING SIGN POST WITH 2" SQUARE 12 GAUGE PERFORATED POST
- IS FURNISH AND INSTALL ROADSIDE SIGN(S) OR SNS WITH/WITHOUT POST
- RS REMOVE SIGN(S) WITH/WITHOUT POST AS NOTED ON PLAN
- RL RELOCATE EXISTING SIGN(S) TO EXISTING POST OR INSTALL POST (IF APPLICABLE)
- S EXISTING SIGNALIZED INTERSECTION
- + PROPOSED SIGN (ONE POST)
- + PROPOSED STREET NAME SIGN
- + EXISTING SIGN (ONE POST)
- + EXISTING/PROPOSED SIGN (ON STREET LIGHT)
- + EXISTING STREET NAME SIGN
- + STREET NAME SIGN
- (12')
- 12'

CONSTRUCTION NOTES:

- CONTRACTOR SHALL INSTALL 2 NEW DLCs FOR CHANNELS 5J1L, 2I3U
- CONTRACTOR SHALL INSTALL 2 NEW DLCs FOR CHANNELS 7J5L, 4I7L
- CONTRACTOR SHALL INSTALL 2 NEW DLCs FOR CHANNELS 1I1L, 6J3U
- CONTRACTOR SHALL FURNISH 2-CHANNEL DETECTOR CARD (2 EA)
- CONTRACTOR SHALL INSTALL 2 NEW DLCs FOR CHANNEL 5J1L, 2I3U
- CONTRACTOR SHALL INSTALL 1 NEW DLCs FOR CHANNEL 8J7L
- CONTRACTOR SHALL INSTALL 1 NEW DLCs FOR CHANNEL 4I6L
- CONTRACTOR SHALL INSTALL 2 NEW DLCs FOR CHANNEL 1I1L, 6J3U
- CONTRACTOR SHALL FURNISH 2-CHANNEL DETECTOR CARD (3 EA)
- CONTRACTOR SHALL INSTALL 2 NEW DLCs FOR CHANNELS 4I7U, 4I7L
- CONTRACTOR SHALL FURNISH 2-CHANNEL DETECTOR CARD (1 EA)
- CONTRACTOR SHALL FURNISH AND INSTALL 48" WHITE GLUE DOWN CHANNELIZERS WITH YELLOW RETROREFLECTORS
- CONTRACTOR SHALL INSTALL MEDIAN NOSE DETAIL PER CITY OF RIVERSIDE STD DWG NO. 666 WITHOUT SIGN.


TRAFFIC SIGNAL GENERAL NOTES:

- ALL ITEMS FURNISHED AND ALL WORK TO BE DONE SHALL CONFORM TO THE REQUIREMENTS OF: THE STATE OF CALIFORNIA, DEPARTMENT OF TRANSPORTATION (CALTRANS) STANDARD PLANS AND SPECIFICATIONS, DATED 2018; THE CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES ADOPTED 2014; AND THE SPECIAL PROVISIONS.
- UTILITIES SHOWN ON THE PLAN ARE CORRECT AND ACCURATE TO THE EXTENT OF AVAILABLE RECORDS. THE CONTRACTOR IS REQUIRED TO TAKE STEPS TO ASCERTAIN THE EXACT LOCATION OF ALL KNOWN SUBSTRUCTURES PRIOR TO DOING WORK THAT MAY DAMAGE OR INTERFERE WITH SUCH FACILITIES ("UNDERGROUND SERVICE ALERT" (800) 227-2600).
- UNLESS SHOWN OTHERWISE, INDUCTIVE LOOPS SHALL BE MODIFIED TYPE "D" & TYPE "E" WITH 10', 15' AND 30' SPACING IN THE DIRECTION OF TRAVEL. NECESSARY STRIPING SHALL BE LOCATED PRIOR TO POSITIONING LOOPS. LOOPS SHALL BE SEALED WITH HOT MELT SEALANT. SEE DETAIL.
- UNDERGROUND SIGNAL CONDUCTORS SHALL NOT BE SPLICED.
- THE CONTRACTOR SHALL VERIFY WITH THE ENGINEER THE PRECISE FIELD LOCATIONS OF ALL TRAFFIC SIGNAL EQUIPMENT PRIOR TO THE INSTALLATION.
- ALL LANDSCAPING WHICH IS DAMAGED BY CONSTRUCTION ACTIVITIES SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE CITY AND THE PROPERTY OWNER.
- DAMAGED SIDEWALK CONCRETE SHALL BE REPLACED PER CITY OF RIVERSIDE STANDARD.
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO FURNISH AND INSTALL ANY ADDITIONAL LOAD SWITCHES AND/OR DETECTOR CARDS, IF NECESSARY, FOR THE PROPOSED OPERATION.

(R-4484)


2019/2020 ARTERIAL AND MINOR STREETS MAINTENANCE, PHASE 1

<p>Under Ground Service Alert of Southern California Call: TOLL FREE 1-800-227-2600 TWO WORKING DAYS BEFORE YOU DIG</p>	<p>ENGINEER IN RESPONSIBLE CHARGE NATHAN T. MUSTAFA R.C.E. No. 83654 EXPIRES: 3-31-21 DATE: 1/28/21</p>		<p>CITY OF RIVERSIDE, CALIFORNIA DEPARTMENT OF PUBLIC WORKS</p> <p>APPROVED BY: <i>FM</i> DATE: 1/28/21 ENGINEERING MANAGER PRINCIPAL ENGINEER TRAFFIC DIVISION CONSTRUCTION ADMIN.</p>	<p>SIGNING AND STRIPING PLAN</p> <p>INDIANA AVENUE FROM PIERCE STREET TO LA SIERRA AVENUE</p> <p>SCALE: 1" = 40' WORK ORDER #2002496</p>	<p>XL-805</p> <p>SHEET 01 OF 04 FILE NAME: XL805.DWG</p>
---	--	--	--	--	---




CONSTRUCTION NOTES (THIS SHEET):

SEE NOTES ON SHEET 01 (PLAN NO. XL-805)




LOCATION 4
2019/2020 ARTERIAL AND MINOR
STREETS MAINTENANCE, PHASE 1



Under Ground Service Alert of Southern California
Call: TOLL FREE 1-800-227-2600
TWO WORKING DAYS BEFORE YOU DIG

ENGINEER IN RESPONSIBLE CHARGE
NATHAN T. MUSTAFA
R.C.E. No. 83654 EXPIRES: 3-31-21
DATE 1/28/21





MARK	REVISIONS	APPR. DATE

CITY OF RIVERSIDE, CALIFORNIA DEPARTMENT OF PUBLIC WORKS			
APPROVED BY	BY	DATE	APPROVED BY
ENGINEERING MANAGER	Fm	1/29/21	CITY ENGINEER
PRINCIPAL ENGINEER			
TRAFFIC DIVISION			
CONSTRUCTION ADMIN.			
DESIGNED BY	FDM	DRAWN BY	FDM
CHECKED BY	NTM	DATE	JAN 28, 2021

SIGNING AND STRIPING PLAN
INDIANA AVENUE
FROM PIERCE STREET
TO LA SIERRA AVENUE

XL-805
SHEET 2 OF 4
FILE NAME: XL805.DWG

SCALE: 1" = 40' WORK ORDER #2002496



STRIPING/SIGNAGE QUANTITIES - XL-805


ITEM	DESCRIPTION	QUANTITY	UNIT
1	DETAIL 9 - 4" WIDTH	15	LF
2	DETAIL 9	9,590	LF
3	DETAIL 22 - 4" WIDTH	360	LF
4	DETAIL 22	5,550	LF
5	DETAIL 25A	125	LF
6	DETAIL 27B	1,130	LF
7	DETAIL 29	2,540	LF
8	DETAIL 32	5,100	LF
9	DETAIL 36	110	LF
10	DETAIL 38	1,540	LF
11	DETAIL 38A	275	LF
12	DETAIL 40 - 4" WIDTH	20	LF
13	4" SOLID WHITE	20	LF
14	6" SOLID WHITE	600	LF
15	8" SOLID WHITE	166	LF
16	12" SOLID WHITE	365	LF
17	PAVEMENT LEGENDS/MARKINGS - WHITE	865	SF
18	PAVEMENT LEGENDS/MARKINGS - YELLOW	1,750	SF
19	ROADSIDE SIGN - ONE POST	1	EA
20	ROADSIDE SIGN - NO POST	3	EA
21	SNS - ONE POST	2	EA
22	SNS - NO POST	1	EA
23	REMOVE SIGN - ONE POST	2	EA
24	REMOVE SIGN - NO POST	10	EA
25	TYPE "D" LOOP DETECTOR	20	EA
26	TYPE "E" LOOP DETECTOR	49	EA
27	2-CHANNEL DETECTOR CARD	6	EA
28	DLC - DETECTOR LOOP CABLE	1,679	LF
29	SC - SPLICE NEW TO EXISTING	12	EA
30	48" CHANNELIZERS	26	EA
31	MEDIAN NOSE DETAIL - W/O SIGN	2	EA

SNS DETAILS - XL-805

INTERSECTION	PANEL No. 1	PANEL No. 2
INDIANA AVE & SAYWARD CIR	Indiana Ave 11600	Sayward Cir 11600
INDIANA AVE & CAPITOL DR	Indiana Ave 11600	Capitol Dr 11600
INDIANA AVE & REVERE RD	Indiana Ave 11600	Revere Rd 3400

CONSTRUCTION NOTES (THIS SHEET):

SEE NOTES ON SHEET 01 (PLAN NO. XL-805)



Under Ground Service Alert of Southern California
 Call: TOLL FREE 1-800-227-2600
 TWO WORKING DAYS BEFORE YOU DIG

ENGINEER IN RESPONSIBLE CHARGE
 NATHAN T. MUSTAFA
 R.C.E. No. 83654 EXPIRES: 3-31-21
 DATE 1/28/21

PROFESSIONAL ENGINEER
 NATHAN T. MUSTAFA
 No. 83654
 Exp. 03-31-21
 CIVIL
 STATE OF CALIFORNIA

DESIGNED BY	FDM	DRAWN BY	FDM	CHECKED BY	NTM
APPROVED BY	BY	DATE	APPR.	DATE	
ENGINEERING MANAGER	EM	1/28/21			
PRINCIPAL ENGINEER					
TRAFFIC DIVISION					
CONSTRUCTION ADMIN.					

CITY OF RIVERSIDE, CALIFORNIA
DEPARTMENT OF PUBLIC WORKS

SIGNING AND STRIPING PLAN
INDIANA AVENUE
FROM PIERCE STREET
TO LA SIERRA AVENUE

XL-805
 SHEET 4 OF 4
 FILE NAME: XL805.DWG

LOCATION 4
 2019/2020 ARTERIAL AND MINOR
 STREETS MAINTENANCE, PHASE 1

SCALE: 1" = 40' WORK ORDER #2002496

DATE: JAN 28, 2021