

THE GROVE VILLAGE - PROPOSED RAMP PLAN

* CONCRETE SWITCHBACK RAMP.
 • MATERIAL:
 - CONCRETE
 - RAILS
 - RETAINING WALL TO PROTECT HOUSE STRUCTURAL
 ESTIMATED COST \$ 20,000.

37' w/ 30" DROP
 TO STEEP, NOT ADA COMPLIANT 15%.
 RAMP MTL:
 PAVERS
 NO RAILINGS
 ESTIMATED COST \$ 5,000

RECOMMENDED RAMP
 60' w/ 12" DROP
 ADA RAMP
 RAMP MTL:
 • PAVERS
 NO RAILINGS
 ESTIMATED COST \$ 5,000
 INCLUDES:
 - RELOCATED (2) UG DRAINS

RAMP IS TOO STEEP
 NOT ADA COMPLIANT
 ESTIMATE COST OF \$ 7,000
 MATERIAL -
 • PAVERS

DSCAPE TIMBERS -
 CHANGE BETWEEN BEDS
 INCE (BLACK) W/ 1" SQ. HOLES -
 MBERS.

