



BILL OF MATERIALS	
ITEM	QUANTITY
① 16" - 54" WATER MAIN	PER PLAN
② 6" FLANGED OUTLET PER CWD 300	1
③ 6" x 12" FLANGED STEEL PIPE	2
④ 6" FLANGED STEEL PIPE	VARIES
⑤ 6" VALVE (FL x FL)	1
⑥ 6" 90° STEEL ELL (FL x FL)	2
⑦ 6" BLIND FLANGE	1
⑧ METER BOX (TRAFFIC RATED BOX & LID)	1

NOTES:

- CONTRACTOR SHALL LEAVE END CAP IN PLACE UNTIL FINAL CONNECTION BY CITY FORCES



WATER DISTRIBUTION & TRANSMISSION
PIPELINE CONSTRUCTION METHODS

16" THROUGH 54" CML&C STEEL
TEMPORARY CONSTRUCTION END CAP
FOR FLUSHING, TESTING, & CHLORINATION